BBS Timbers Plywood and Panels

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 2
- Performance 4
- Selection - Bendy Plywood 4
- Selection - Birch HPL Plywood 5
- Selection - Birch Plywood 5
- Selection - Brownwood Plywood 8
- Selection - Gaboon BS1088 Premium Marine Ply 9
- Selection - Gaboon Lite Premium Ply 11
- Selection - Meranti BS1088 Marine Plywood 12
- Selection - Mixed Hardwood Plywood 13
- Selection - Construction Plywood 14
- Finish Coating 16
- Co-operation 16
- Workmanship 16
- Delivery and Handling 17
- Preparation 17
- Installation 19
- Fixing 21
- Completion 22

Compliances 22

SMARTSPEC

1 Specification Details

Trade Sections: Carpentry, Joinery
Description: BBS Timbers range of plywood and timber panel systems
Keywords: BBS Timber plywood panel interior linning

2 Clauses

2.1 Scope

Help Note:
For further information, or in the situation of conflict or doubt, contact BBS Timbers Ltd on (website) http://bbstimbers.co.nz , (call) 0800 227 862, or (email) office@bbstimbers.co.nz

2.1.1 Scope

Supply and install BBS Plywood and Panel Interior Linings, as specified herein, to the locations identified on the drawings, complete with all components and accessories required for proper installation and performance. All aspects of this work shall be in complete accordance with BBS Timbers Ltd technical literature (check http://bbstimbers.co.nz , or email office@bbstimbers.co.nz, or call 0800 227 862for the latest editions), other relevant product manufacturers' recommendations, and the New Zealand Building Code.

No substitutions are permitted for BBS Timbers Ltd Interior Linings.

This specification should be read in conjunction with other specification sections, in particular Painting & Decorating, as they are interrelated.

2.2 Requirements

Help Note:
For further information, or in the situation of conflict or doubt, contact BBS Timbers Ltd on (website) http://bbstimbers.co.nz , (call) 0800 227 862, or (email) office@bbstimbers.co.nz

2.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

2.2.2 Substitutions

BBS Plywood and Panel Interior Linings materials shall be as specified herein and as indicated on the design drawings. The substitution of the specified BBS Plywood and Panel Interior Linings materials for an alternative brand or material is not permitted under any circumstances.

The substitution of a specified BBS Plywood and Panel Interior Linings materials for an alternative BBS Plywood and Panel Interior Lining materials by the Contractor shall only be permitted with the

Contract Administrator's written authorisation, and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate an alternative BBS Plywood and Panel Interior Linings material to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor.

2.2.3 Samples

Submit a clearly identified, 300 x 300mm sample of each BBS Plywood and Panel Interior Lining specified for assessment by the Contract Administrator - do not proceed until the samples have been approved.

2.2.4 Reserve Material

On completion of the installation works supply and deliver to the Principal/Owner the specified quantity of BBS Plywood and Panel Interior Lining sheets - new, unused and free from damage and defects - for each plywood lining material specified.

Quantity:

2.2.5 Producer Statement (other manufacturer's system)

Producer Statement PS1 - where required. Where BBS Plywood and Panel Interior Linings are installed as a component of another manufacturer's proprietary system, the system manufacturer shall furnish a completed Producer Statement PS1 (Design) as confirmation that the specified proprietary system as designed and documented complies with the relevant clauses of the New Zealand Building Code. The PS1 Producer Statement shall not serve as a product warranty or guarantee of compliance.

2.2.6 Quality Assurance

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of the works are carried out to the highest standard.

Ensure that the installation and finishing of BBS Plywood and Panel Interior Lining comply in all respects with the approved design drawings and specifications, and Building Consent.

2.2.7 Inspections & Reporting

BCA inspections of the works shall take place at each of the stages as scheduled in the Building Consent. Confirm a written programme to facilitate these inspections, including notification when each stage of the work is ready for inspection.

Carry out all necessary pre-installation and installation inspections for each area of the works.

Complete all necessary Pre-Installation Checklists, and all necessary Installation Checklists.

Complete all necessary Sign-Off Certificates before handing over completed work.

2.2.8 Defective Materials & Work

Should defective materials and/or work be found at any time before the final acceptance of the work, it shall be rejected. Rejected BBS Timber Plywood Interior Linings work shall be repaired and/or replaced to the satisfaction of the Contract Administrator, without delay and at no additional cost to the Principal.