Forté Millboard Decking

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 2
- Millboard Enhanced Grain 4
- Millboard Weathered Oak 8
- Accessories 11
- Co-operation 11
- Workmanship 12
- Delivery & Handling 12
- Preparation & Installation 13
- Completion & Maintenance 14

Compliances 15

SWARTSPEC

1 Specification Details

Trade Sections: Carpentry
Description: Decking
Keywords: Forte, forte, Carpentry, Forte Flooring, Millboard Decking, composite decking planks, prefinished decking, deck board, deck plank, decks, boardwalk decking, boardwalk planks, open deck, slat deck, slatted deck, textured decking, textured plank, imitation timber decking, imitation wood, slip resistant decking, slip-resistant decking, Millboard Enhanced Grain, Millboard Weathered Oak.

2 Clauses

2.1 Scope

Help Note:
For technical advice and specification guidance, contact Forté Flooring Ltd on 0800 445 494

For technical information on products to attach to this project, please visit Forté Decking

2.1.1 Scope

Supply and install Millboard Decking, as specified herein, to the locations, layout and details shown on the design drawings, complete with all associated components and accessories required for proper installation and performance. All aspects of this work shall be in complete accordance with the manufacturer's technical literature and Forté Flooring Ltd requirements (check www.forte.co.nz, or e-mail info@forte.co.nz, or call 0800 445 494 for the latest editions), and other relevant product manufacturers' recommendations.

No substitutions are permitted for Millboard Decking.

2.1.2 Extent of Work

The following is a list and general description of the extent of the Millboard Decking works, which are more specifically defined in the contract documents, required for the completion of the contract works:

2.2 Requirements

Help Note:
Clause options listed below are optional - as applicable, select only those options according to project requirements.

For technical advice and specification guidance, contact Forté on 0800 445 494.

SMARTSPEC

2.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

2.2.2 Warranty - 25 Year Residential Warranty

Millboard Decking 25 Year Residential Warranty - according to the warranty conditions.
- 25 Years' Warranty for all Millboard Decking installed.
- Provide this warranty on the manufacturer's standard warranty form.
- Commence the warranty from the date of practical completion of the contract works.

2.2.3 Warranty - 5 Year Limited Warranty

Millboard Decking 5 Year Limited Warranty - according to the warranty conditions.
- 5 Years' Warranty for all Millboard Decking installed.
- Provide this warranty on the manufacturer's standard warranty form.
- Commence the warranty from the date of practical completion of the contract works.

2.2.4 Substitutions

Millboard Decking shall be as specified herein and as indicated on the design drawings. The substitution of Millboard Decking for an alternative brand or material is not permitted under any circumstances.

The substitution of a specified Millboard Decking product for an alternative Millboard Decking product by the Contractor shall only be permitted with the Contract Administrator's written authorisation, and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate alternative Millboard Decking to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor.

2.2.5 Evidence of Slip Resistance

If requested, provide certified evidence showing the slip resistance classification of the Millboard Decking, as specified and installed, complies with NZBC D1/AS1, 2.1.

2.2.6 Quality Assurance

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of the works are carried out to the highest standard.

2.2.7 Inspection & Reporting

BCA inspections of Millboard Decking works shall take place at each of the stages as scheduled in the Building Consent. Confirm a written programme to facilitate these inspections, including notification when each stage of the work is ready for inspection.
Carry out all necessary pre-installation, installation and sign-off inspections of the works for each area of work in accordance with Forté Flooring Ltd requirements and industry best-practice recommendations.