Resene PSL Plaster Cladding

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- General 2
- Preparation 3
- Workmanship 3
- Substrate 4
- Installation 6
- Cavity Battens 10
- Vented Cavity Base Material 10
- Render & Mesh Coat 11
- Levelling Coat 12
- Texture Coat 13
- Protective Finish Coat 16
- Work 16

Compliances 16

SMARTSPEC

1 Specification Details

Trade Sections: Plasterwork
Description:
Keywords: Plasterwork, Resene Construction Systems, plaster, plastering, plaster cladding, plastered cladding, cladding, plaster systems, plaster cladding systems, plastered cladding systems, cladding systems, wall cladding plaster, plastered wall cladding systems, exterior wall cladding systems, plastered exterior wall cladding systems, plastered walls, wall plaster, plastered facade systems, facade plaster systems, plastered polystyrene cladding, plastered EPS cladding, plastered Graphix cladding, plastered precast concrete panels, plastered concrete, plastered AAC, plastered Enduron, plastered concrete block, plastered concrete blockwork, plastered fibre cement sheet, plastered fibre-cement sheet, plastered masonry block, ERM Coarse Render, Coarse Render, Thermabase Render, Tecstop Render, Multiplast All Purpose, Brick and Block Render, Bagged Brick and Block System, Ezytex Plaster, Float Finish, Sponge Finish, Fine Finish, Scratch & Drag Finish, Adobe Finish,

SMARTSPEC

2 Clauses

2.1 Scope

Help Note:
For technical information on products to attach to this project, please visit https://productspec.co.nz/en/supplier/resene construction systems

2.1.1 Scope

All of the wall surfaces identified for Resene PSL Plaster Cladding on the drawings, together with all associated flashings, reveals finishing and other details. Note that no substitutions are permissible for any of the products specified herein.

2.2 General

2.2.1 General

All materials and workmanship incorporated into the construction by this subcontract shall be such as to qualify in every detail and respect for the Resene PSL 15 year Product Performance Warranty and the 5 year Workmanship Warranty.

If the Cladding Plasterer considers that general conditions of previous work is unsatisfactory to ensure a proper finish for the cladding work required they shall give immediate notice to the Contractor or

Architect/Designer as appropriate and shall not proceed until necessary improvements have been made. Failing such notice the Cladding Plasterer will not be relieved of the responsibility for a poor finish due to such unsatisfactory condition.

The Contractor and Subcontractors affected shall be jointly and severally responsible for completion of the whole of the works in a completely watertight condition and shall therefore examine all details to be satisfied that this condition can be achieved. If any detail is considered unsatisfactory the Architect/Designer shall be immediately notified and they will then either interpret the detail to the Contractor's satisfaction, or accept responsibility for watertightness at the points in question, always assuming reasonable workmanship.

2.3 Preparation

2.3.1 Preparation

Co-ordinate with all other trades to ensure appropriate substrate conditions to achieve first class results.

Check that any other fixings, brackets or electrical or plumbing elements that in any way affect the cladding plaster system are correctly in place, are flashed or taped as required, and are appropriate for finish sealing.

Install preprimed Resene PSL uPVC flashings exactly as noted, detailed, or recommended, and saddle and apron flashings, balustrades and handrails junctions, etc. as detailed or required, using sealants, adhesives and fixings as recommended by Nuplex.

Prepare for control joints in the positions shown on the drawings and elsewhere as required to fully comply with Resene PSL recommendations, and arrange for a Resene PSL technical inspector to confirm that the control joints are in their appropriate positions and they are all that are required. Prepare drained movement junctions at all positions where the Resene PSL Plaster Cladding abuts other materials.

Mask all adjacent windows, doors or other joinery, roofs, plumbing or electrical items, and prefinished surfaces etc. that could possibly be marked by the render work, and use drop cloths and ground covers to keep the works area clean.

Immediately prior to applying coatings check the full substrate surfaces and brush, scrub, wash, or rasp as required to remove any dirt, dust, oxidation, formwork release agents or similar. Prime to improve adhesion or damp down to control suction before applying render on hard or smooth or absorbant surfaces.

2.4 Workmanship

2.4.1 Workmanship

All work shall be carried out by experienced and skilled PPCS (Proprietary Plaster Cladding Systems) Registered Tradesmen licensed to apply Resene PSL Systems exterior cladding renders, and be in

SMARTSPEC