# Specialized EZpanel AAC Panel Cladding System

## TABLE OF CONTENTS


Specification Details ..... 2
Clauses ..... 2
- Scope ..... 2
- Requirements ..... 3
- EZpanel Cladding System ..... 5
- EZpanel Plaster System ..... 6
- Components & Accessories ..... 6
- Co-operation ..... 8
- Workmanship ..... 8
- Delivery & Handling ..... 9
- Preparation ..... 10
- Installation ..... 12
- Fixing ..... 15
- Plaster System - Base Coat ..... 18
- Plaster System - Finish Coat ..... 19
- Exterior Paint System ..... 21
- Completion ..... 23

Compliances ..... 23


SMARTSPEC

# 1 Specification Details

Trade Sections: Plasterwork
Description:
Keywords: Plasterwork, Specialized Construction Products, Specialized EZpanel AAC Panel Cladding System,
cladding, cladding systems, plastered wall cladding systems, exterior wall cladding systems, plastered exterior wall cladding systems, stucco plaster cladding systems, insulated plaster cladding systems, plastered panel veneer, plastered veneer, AAC, (AAC), AAC panels, autoclaved aerated concrete, autoclaved aerated concrete panel, aerated concrete panel, AAC cladding, wall cladding, plastered AAC, plastered autoclaved aerated concrete panels, AAC lightweight panels, AAC light weight panels, external cladding, external wall cladding, closed cavity, closed cavity construction, closed wall cavity, closed wall cavity cladding, closed wall cavity panels, plastered façade systems, plastered AAC cladding, plastered lightweight concrete cladding, plastered light-weight concrete cladding, plastered light weight concrete cladding, plastered LWC cladding, plastered AAC panels, plaster, plastering, plaster finishes, plastered cladding, plaster systems, plaster cladding systems, wall cladding plaster systems, plastered exterior wall cladding, plastered walls, wall plaster, lightweight concrete plaster systems, light-weight concrete plaster systems, light weight concrete plaster systems, LWC plaster systems, precast concrete plaster systems, concrete plaster systems, AAC panel plaster systems, Powerflex plaster, fine spray texture plaster, float finish plaster, spanish plaster, stucco texture plaster, Gronopor Fine 1.0mm acrylic texture, Granopor Top 1.5mm acrylic texture, Plastershield paint system,

# 2 Clauses

## 2.1 Scope

*Help Note:*
For technical information on products to attach to this project, please visit https://productspec.co.nz/en/supplier/specialized construction products

### 2.1.1 Scope

Supply and install Specialized EZpanel AAC Panel Cladding System, as specified herein, to the locations identified on the design drawings, complete with all system components and accessories required for proper installation and performance. All aspects of this work shall be in complete accordance with the Specialized Construction Products (SCP) technical literature, including the EZpanel Specification and EZpanel Installation Guide and detail drawings (check www.specialized.co.nz, or email info@specialized.co.nz, or call 0800 0800 79 for the latest editions), BRANZ Appraisal No.649, and other relevant product manufacturers' recommendations.

SKYMASTER SPEC

No substitutions are permitted for Specialized EZpanel AAC Panel Cladding System.

For the purpose of this specification, the Specialized EZpanel AAC Panel Cladding System is referred to as 'EZpanel Cladding', and Specialized Construction Products is referred to as 'SCP'. All associated SCP technical literature, including the EZpanel Installation Guide and EZpanel Specification and detail drawings, and the BRANZ Appraisal, is collectively referred to as the 'Technical Literature'.

All PVC flashings, fibreglass mesh, resin, fixings and plaster components used for the EZpanel Cladding system must be supplied by SCP or one of its certified distributors.

The EZpanel Cladding plaster system must be finished with Dulux AcraTex 955 AcraSheild Advance100% acrylic paint system in accordance with SCP paint specifications.

#### 2.1.2 Extent of Work

The following is a list and/or general description of the extent of the EZpanel Cladding works, which are more specifically defined in the contract documents, required for the completion of the contract works:

## 2.2 Requirements

#### 2.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

#### 2.2.2 Warranty - System

SCP Materials Warranty - according to the warranty terms and conditions:

- 15-Year Warranty for the failure of the EZpanel Cladding system under normal environmental and use conditions.
- Provide this warranty on the manufacturer's standard warranty form.
- Commence the warranty from the date of practical completion of the works.

#### 2.2.3 Warranty - Workmanship

Workmanship Warranty:

- 5-Year Warranty for workmanship and execution of the EZpanel Cladding.
- Commence the warranty from the date of practical completion of the contract works.

#### 2.2.4 Substitutions

EZpanel Cladding shall be as specified herein and on the design drawings. The substitution of EZpanel Cladding for an alternative brand or cladding system or material is not permitted under any circumstances.

SMARTSPEC