Plymasters Exterior or Construction Lining System

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 2
- Performance 4
- Construction Plywood Systems 4
- Transport Plywood Systems 8
- Ancillary Components & Accessories 10
- Surface Appearance 10
- Finish Coating 11
- Co-operation 11
- Workmanship 11
- Delivery & Handling 12
- Preparation 13
- Installation 14
- Fixing 14
- Completion 15

Compliances 15

SMARTSPEC

1 Specification Details

Trade Sections: Concrete, Carpentry, Joinery
Description: Exterior or Construction Lining system
Keywords: Plywood, exterior Linings, Prefinished Veneer Panels, Plymasters, Plywood, MDF, Laminate Panels, Marine Plywood, Timber Veneer Panels, Concrete substrate, concrete shutters, hoarding, construction ply

2 Clauses

2.1 Scope

Help Note:
For technical enquiries contact Plymasters on 0800344112 or e-mail sales@plymasters.co.nz or head to the website www.plymaster.co.nz

For technical information on products to attach to this project, please visit https://productspec.co.nz/en/supplier/plymasters

2.1.1 Scope

The following is a list and/or general description of the extent of the Plymasters Exterior or Construction Lining System works, which are more specifically defined in the contract documents, required for the completion of the contract works:

Supply and install Plymasters Exterior or Construction Lining System, as specified herein, to the locations identified on the drawings, complete with all components and accessories required for proper installation and performance. All aspects of this work shall be in complete accordance with Plymasters 'technical literature' (check https://plymasters.co.nz/categories/products, or email sales@plymasters.co.nz, or call 0800 344 112 for the latest editions), other relevant product manufacturers' recommendations, and the New Zealand Building Code.

No substitutions are permitted for Plymasters Exterior or Construction Lining System products.

This specification should be read in conjunction with other specification sections, in particular Painting & Decorating, as they are interrelated.

2.2 Requirements

2.2.1 Safety:

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes

SMARTSPEC

of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

2.2.2 Warranty – Product:

Plymasters Product Warranty - as applicable and according to warranty terms and conditions:

- Three year warranty for Plymasters Exterior or Construction lining System materials.
- Provide the warranty on the Plymasters standard warranty form.
- Commence the warranty no later than three days after delivery.

2.2.3 Substitutions:

Plymasters Exterior or Construction Lining System materials shall be as specified herein and as indicated on the design drawings. The substitution of the specified Plymasters Exterior or Construction Lining System materials for an alternative brand or material is not permitted under any circumstances.

The substitution of a specified Plymasters plywood material for an alternative Plymasters plywood material by the Contractor shall only be permitted with the Contract Administrator's written authorisation, and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate an alternative Plymasters plywood material to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor

2.2.4 Samples:

Submit a clearly identified, 300 x 300mm sample of each Plymasters plywood material specified for assessment by the Contract Administrator - do not proceed until the samples have been approved.

2.2.5 Producer Statement (other manufacturer's system):

Producer Statement PS1 - where required. Where Plymasters Exterior or Construction Lining System products are installed as a component of another manufacturer's proprietary system, the system manufacturer shall furnish a completed Producer Statement PS1 (Design) as confirmation that the specified proprietary system as designed and documented complies with the relevant clauses of the New Zealand Building Code.

The PS1 Producer Statement shall not serve as a product warranty or guarantee of compliance

2.2.6 Quality Assurance:

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of the works are carried out to the highest standard.

Ensure that the installation and finishing of Plymasters Exterior or Construction Lining System comply in all respects with the approved design drawings and specifications, and Building Consent.