GIB® Fire Rated Systems

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 3
- Performance 4
- Wall Systems - 2-Way FRR 5
- Wall Systems - 1-Way FRR 10
- Floor/Ceiling Systems 11
- Floor/Ceiling Systems - Suspended Grid 13
- Ceiling Systems 14
- GIB® Fyreduct™ 15
- GIB® Ventshaft 16
- GIB® Shaftwall 17
- GIB® Fire Rated Protection of Steel 18
- Components & Accessories 21
- Co-operation 21
- Workmanship 21
- Delivery & Handling 22
- Preparation 23

Compliances 24

SMARTSPEC

1 Specification Details

Trade Sections: Carpentry
Description:
Keywords: Carpentry, GIB, Winstone Wallboards, GIB® Fire Rated Systems, plasterboard lining, wall lining, ceiling lining, interior lining, fire-resistant lining, fire resistant lining, fire-resistant plasterboard, fire resistant plasterboard, plasterboard lining systems, fire rated wall systems, fire rated ceiling systems, fire-rated wall systems, fire-rated ceiling systems, GIB® Fyreduct™, GIB® Ventshaft, GIB® Shaftwall, GIB® Fire Rated Protection of Columns and Beams System, GIB Fyreline®,

2 Clauses

2.1 Scope

Help Note:
For further information and technical advice about GIB® Fire Rated Systems contact the GIB® Helpline on 0800 100 442.

For technical information on products to attach to this project, please visit productspec.co.nz/en/supplier/gib%c2%ae.

2.1.1 Scope

Supply and install the specified GIB® Fire Rated Systems to the locations identified on the drawings, incorporating GIB® plasterboards and all system components and accessories required for proper installation and performance. All aspects of this work shall be in complete accordance with the GIB® Fire Rated Systems Specification and Installation Manual and the current GIB® Site Guide (check www.gib.co.nz, or call 0800 100 442 for the latest editions), BRANZ Appraisal No.289, other relevant product manufacturers' recommendations, and as shown on the drawings.

No substitutions are permitted for GIB® Fire Rated Systems, GIB® Plasterboard Linings, or GIB® System components and accessories.

This specification section must be read in conjunction with the GIB® Plasterboard Linings specification and relevant GIB® Systems specifications, and other specification sections, as they are interrelated.

For the purpose of this specification, the GIB® Fire Rated Systems Specification and Installation Manual (2012) is referred to as the GIB® Fire Rated Systems Manual.

SMARTSPEC

2.2 Requirements

Help Note:
For further information and technical advice about GIB® Fire Rated Systems contact the GIB® Helpline on 0800 100 442.

2.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

2.2.2 Warranty

GIB® Product & System Warranty:
- 10 Years Warranty - for all GIB® Products and Systems installed, according to warranty conditions.
- Provide the GIB® Product & System Warranty on the manufacturer's standard warranty form.
- Commence the warranty from the date of practical completion of the contract works.

Include with the warranty: a copy of the completed GIB® Installation Sign-Off sheet, and the GIB® Plasterboard Lining Systems Care and Maintenance bulletin.

2.2.3 AWCI Membership

Installation of GIB® Fire Rated Systems shall be carried out by a registered member of the Association of Wall and Ceiling Industries of New Zealand Inc. (AWCI). If not already provided and if requested, submit evidence of AWCI membership and relevant experience.

2.2.4 Quality Assurance

Ensure that the installation and finishing of GIB® Fire Rated Systems comply in all respects with the approved design drawings and specifications, and Building Consent.

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of work are carried out to the highest standard.

2.2.5 Inspection & Acceptance of GIB® Fire Rated Systems

Carry out all necessary pre-installation, installation and finishing inspections necessary for GIB® Fire Rated Systems for each area of work in accordance with the requirements of the GIB® Fire Rated Systems Manual, GIB® Site Guide, and BRANZ Appraisal No.289.

Complete the GIB® Site Guide Pre-Installation Checklist prior to installing GIB® plasterboard linings.

Complete the GIB® Plasterer/Stopper Installation Sign-Off Certificate upon completion and before handover for subsequent decoration.

SMARTSPEC