Plytech Plywood Interior Linings

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 2
- Performance 4
- Plytech Prefinished Plywood - Walls 5
- Plytech Prefinished Plywood - Ceilings 11
- Plytech Unfinished Plywood - Walls 16
- Plytech Unfinished Plywood - Ceilings 39
- Plytech Prefinished Non-Plywood - Walls 55
- Ancillary Components & Accessories 58
- Finish Coating 59
- Co-operation 60
- Workmanship 60
- Delivery & Handling 60
- Preparation 61
- Installation 62
- Fixing 66
- Completion 71

Compliances 71

SMARTSPEC

1 Specification Details

Trade Sections: Carpentry
Description:
Keywords: Carpentry, Plytech, interior plywood linings, wall lining, ceiling lining, plywood panels, plywood sheet, plywood walls, plywood ceilings,

2 Clauses

2.1 Scope

Help Note:
If in doubt about any aspect of your specification please email Plytech International Ltd at sales@plytech.co.nz, or call 0800 900 905.

For technical information on products to attach to this project, please visit https://productspec.co.nz/en/supplier/plytech

2.1.1 Scope

Supply and install Plytech Plywood Interior Linings, as specified herein, to the locations identified on the drawings, complete with all components and accessories required for proper installation and performance. All aspects of this work shall be in complete accordance with Plytech International Ltd technical literature (check www.plytech.co.nz, or email sales@plytech.co.nz, or call 0800 900 905 for the latest editions), other relevant product manufacturers' recommendations, and the New Zealand Building Code.

No substitutions are permitted for Plytech Plywood Interior Linings.

This specification should be read in conjunction with other specification sections, in particular Painting & Decorating, as they are interrelated.

2.1.2 Extent of Work

The following is a list and/or general description of the extent of the Plytech Plywood Interior Linings works, which are more specifically defined in the contract documents, required for the completion of the contract works:

2.2 Requirements

Help Note:
Clause options listed below are optional - as applicable, select only those options according to project requirements.

If in doubt about any aspect of your specification please email Plytech International Ltd at sales@plytech.co.nz, or call 0800 900 905.

SMARTSPEC

2.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

2.2.2 Warranty - Product

Plytech International Ltd Product Warranty - as applicable and according to warranty terms and conditions.

- For Plytech interior lining materials.
- Provide the warranty on the Plytech International Ltd standard warranty form.
- Commence the warranty no later than three days after delivery.

2.2.3 Warranty - Installation

Installer's Installation Warranty - according to warranty terms and conditions.

- 2 Years Workmanship Warranty for all Plytech Plywood Interior Linings installed.
- Provide the Installation Warranty on the Installer's Standard Warranty Form.
- Commence the warranty from the date of practical completion of the contract works.

2.2.4 Substitutions

Plytech Plywood Interior Linings materials shall be as specified herein and as indicated on the design drawings. The substitution of the specified Plytech Plywood Interior Lining materials for an alternative brand or material is not permitted under any circumstances.

The substitution of a specified Plytech plywood material for an alternative Plytech plywood material by the Contractor shall only be permitted with the Contract Administrator's written authorisation, and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate an alternative Plytech plywood material to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor.

2.2.5 Samples

Submit a clearly identified, 300 x 300mm sample of each Plytech plywood material specified for assessment by the Contract Administrator - do not proceed until the samples have been approved.

2.2.6 Reserve Material

On completion of the installation works supply and deliver to the Principal/Owner the specified quantity of Plytech Plywood Interior Lining sheets - new, unused and free from damage and defects - for each plywood lining material specified.

Quantity:

2.2.7 Producer Statement (other manufacturer's system)

Producer Statement PS1 - where required. Where Plytech Plywood Interior Linings are installed as a component of another manufacturer's proprietary system, the system manufacturer shall furnish a completed Producer Statement PS1 (Design) as confirmation that the specified proprietary system as