Rinnai Gas Fireplaces

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 3
- Linear Collection 5
- Landscape Series 12
- Compact Series 14
- Ancillary Components 18
- Co-operation 21
- Workmanship 21
- Delivery & Handling 22
- Installation 23
- Completion 25

Compliances 25

SMARTSPEC

1 Specification Details

Trade Sections: Gas, HVAC
Description: Rinnai Gas Fireplaces
Keywords: Linear Collection - Linear 800, Linear 1000, Linear 1500, Linear Indoor-Outdoor
Landscape Series - Evolve 952, Evolve 1252, Symmetry, Arriva
Compact Series - Novo Series (Novo Freestander, Novo Cube, Novo Inbuilt), Neo, Ember, Compact 2
Mesh Guard Peninsular Pack
Outer Finishing Trim
Black magic reflective side panels

2 Clauses

2.1 Scope

Help Note:
This section relates to the supply and installation of Rinnai New Zealand Limited hot water systems. For further information visit www.rinnai.co.nz or info@rinnai.co.nz Phone 0800 746 624.

NOTE: From this section on, read down the right list of Clauses.
Select the Clause followed by the Option/s required.
When the options have been selected the correct Accessories *will display*.
Select Accessories then Option/s as you require.

2.1.1 Scope

Scope
Supply and install Rinnai Gas Fires, as specified herein and indicated on the design drawings, complete with all necessary components and accessories required for proper installation and performance. All aspects of this work shall be in complete accordance with the manufacturer's technical literature (check www.rinnai.co.nz, or email info@rinnai.co.nz, or call 0800 746 624 for the latest editions), the New Zealand Building Code, relevant Regulations and Acts and Standards, and the requirements of the Building Consent.
No substitutions are permitted for Rinnai Gas Fires.

2.1.2 Extent of Work

Extent or Work
The following is a list and/or general description of the extent of the Rinnai Gas Fires works, which are more specifically defined in the contract documents, required for the completion of the contract works:

SMARTSPEC

2.1.3 Substitutions

Substitutions

Rinnai Gas Fires shall be as specified herein and on the design drawings. The substitution of an Rinnai Gas Fire for an alternative brand or type is not permitted under any circumstances.

The substitution of a specified Rinnai gas fire for an alternative Rinnai fire by the Contractor shall only be permitted with the Contract Administrator's written authorisation and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate an alternative Rinnai fire to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor

2.2 Requirements

Help Note:

This section relates to the supply and installation of Rinnai New Zealand Limited hot water systems. For further information visit www.rinnai.co.nz or info@rinnai.co.nz Phone 0800 746 624.

2.2.1 Safety

Safety

Comply with the Gas (Safety and Measurement) Regulations 2010, and the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

2.2.2 Warranty - Product

Warranty - Product

Rinnai Warranty - according to warranty terms and conditions.

- 5 Year Firebox warranty
- 2 Year Total Warranty.
- Provide the warranty on the Rinnai standard warranty form.
- Commence the warranty from the date of purchase.

2.2.3 Warranty - Installation

Warranty - Installation

Installer Installation Warranty - according to warranty terms and conditions.

- 2 Years Workmanship Warranty for Rinnai Gas Fires installed.
- Provide the Installation Warranty on the Installer standard warranty form.
- Commence the warranty from the date of practical completion of the contract works.

2.2.4 Inspections & Reporting

Inspections & Reporting

BCA inspections of the works shall take place at each of the stages as scheduled in the Building Consent. Confirm a written programme to facilitate these inspections, including notification when each stage of the work is ready for inspection.

SMARTSPEC