GIB® Quietline® Reverberation Control Systems

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 2
- Performance 4
- Components & Accessories 5
- Finish Level 8
- Co-operation 8
- Workmanship 9
- Delivery & Handling 9
- Preparation 10
- Installation 11
- Completion 13

Compliances 14

SMARTSPEC

1 Specification Details

Trade Sections: Carpentry, Suspended Ceilings
Description:
Keywords: Suspended ceilings, Carpentry, GIB Quietline, plasterboard, linings, wall lining, ceiling lining, suspended ceiling lining, acoustic plasterboard, acoustic lining, acoustic ceiling lining, acoustic wall lining, acoustic lining, perforated plasterboard, perforated linings, perforated acoustic plasterboard, perforated acoustic linings, Circle 8mm, Random 1 Panel, Random 2 Panel, Leaf 1 Panel,

2 Clauses

2.1 Scope

Help Note:
For further information and technical advice about GIB® Reverberation Control Systems or GIB Quietline® contact the GIB® Helpline on 0800 100 442.

For technical information on products to attach to this project, please visit productspec.co.nz/en/supplier/gib%c2%ae.

2.1.1 Scope

Supply and install GIB® Reverberation Control Systems - GIB Quietline® to the locations identified on the drawings, incorporating GIB Quietline® perforated plasterboard and all system components and accessories required for proper installation and performance. All aspects of this work shall be in complete accordance with the GIB® Reverberation Control Systems Manual and the GIB® Site Guide (check www.gib.co.nz, or call 0800 100 442 for the latest edition), and other relevant product manufacturers' recommendations.

No substitutions are permitted for GIB® Reverberation Control Systems, GIB Quietline®, or GIB® System components and accessories.

This specification section must be read in conjunction with the GIB® Plasterboard Linings specification and relevant GIB® Systems specifications, and other specification sections, as they are interrelated.

For the purpose of this specification, the GIB® Reverberation Control Systems Design and Installation Manual for GIB Quietline® and GIB-Tone® Quiet™ tiles publication is referred to as the 'GIB® Reverberation Control Systems Manual'.

2.2 Requirements

Help Note:
For further information and technical advice about GIB® Reverberation Control Systems or GIB Quietline® contact the GIB® Helpline on 0800 100 442.

SMARTSPEC

2.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

2.2.2 Warranty

GIB® Product & System Warranty:

- 10 Years Warranty - for all GIB® Products and Systems installed, according to warranty conditions.
- Provide the GIB® Product & System Warranty on the manufacturer's standard warranty form.
- Commence the warranty from the date of practical completion of the contract works.

Include with the warranty: a copy of the completed GIB® Installation Sign-Off sheet, and the GIB® Plasterboard Lining Systems Care and Maintenance bulletin.

2.2.3 AWCI Membership

Installation of GIB® Reverberation Control Systems incorporating GIB Quietline® perforated plasterboard lining shall be carried out by a registered member of the Association of Wall and Ceiling Industries of New Zealand Inc. (AWCI). If not already provided and if requested, submit evidence of AWCI membership and relevant experience.

2.2.4 Quality Assurance

Ensure that the installation and finishing of GIB Quietline® perforated plasterboard lining comply in all respects with the approved design drawings and specifications, and Building Consent.

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of work are carried out to the highest standard.

2.2.5 Inspection & Acceptance of GIB® Reverberation Control Systems

Carry out all necessary pre-installation, installation and finishing inspections necessary for GIB® reverberation Control Systems incorporating GIB Quietline® perforated plasterboard lining for each area of work in accordance with the requirements of the GIB® Acoustic Systems Manual and the GIB® Site Guide.

Complete the GIB® Site Guide Pre-Installation Checklist prior to installing GIB® plasterboard linings.

Complete the GIB® Interior Plasterer/Stopper Installation Sign-Off Certificate upon completion and before handover for subsequent decoration.

2.2.6 Defective Materials & Work

Should defective materials and/or work be found at any time before the final acceptance of the work, it shall be rejected. Rejected GIB® Reverberation Control Systems materials and/or work shall be repaired and/or replaced to the satisfaction of the Architect/Designer, without delay and at no additional cost to the Principal.