IBS EUROFloor Systems

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 2
- IBS EUROFloor 3
- Co-operation 4
- Workmanship 5
- Delivery & Handling 5
- Preparation 6
- Installation - Floor 6
- Fixing 7
- Completion 8

Compliances 8

SWARTSPEC

1 Specification Details

Trade Sections: Carpentry
Description: IBS EUROFloor is a OSB3 (Oriented Strand Board) panel. The product is a moisture resistant, engineered structural wood panel made from PEFC forests in Europe. IBS EUROFloor is specifically designed for the New Zealand market.
Keywords: Carpentry, Independent Building Supplies, IBS, EUROFloor, Eurofloor, eurofloor, obs,

2 Clauses

2.1 Scope

Help Note:
Description
IBS EUROFloor is a OSB3 (Oriented Strand Board) panel. The product is a moisture resistant, engineered structural wood panel made from PEFC forests in Europe. IBS EUROFloor is specifically designed for the New Zealand market.

IBS EUROFloor can be used in all wet areas including bathrooms, laundries and showers, this is provided that it has the necessary waterproof membrane. The water impervious membrane must cover the floor and be coved at the walls. Refer to Acceptable Solution E3/AS1.2.12.

For product information and technical advice please info@ibs.co.nz, or call 0800 367 759.
For technical information on products to attach to this project, please visit www.ibs.co.nz

2.1.1 Scope

Supply and install IBS EUROFloor, as specified herein, to the locations identified on the drawings, complete with all accessories required for proper installation. All aspects of this work shall be in complete accordance with relevant, IBS EUROFloor Design and Installation Guide, as well as all technical literature (check www.ibs.co.nz, or email info@ibs.co.nz, or call 0800 500 338 for the latest editions), relevant IBS EUROFloor CodeMark and other relevant product manufacturers' recommendations.

No substitutions are permitted for IBS EUROFloor.

For the purpose of this specification, all relevant IBS EUROFloor technical literature and CodeMark are referred to as the 'Technical Literature'.

2.2 Requirements

Help Note:
For product information and technical advice please info@ibs.co.nz, or call 0800 367 759.
For technical information on products to attach to this project, please visit www.ibs.co.nz

SMARTSPEC

2.2.1 Requirements

Safety

Safety comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

Warranty

IBS EUROFloor Product Warranties - according to warranty terms and conditions:

- 50 Years Warranty for EUROFloor panels supplied by IBS.
- Provide the warranties on the supplier's standard warranty form.
- Commence the warranty from the date of practical completion of the contract works.

Substitutions

IBS EUROFloor shall be as specified herein and on the design drawings. The substitution of the specified IBS EUROFloor OBS materials for an alternative brand or material is not permitted under any circumstances.

The substitution of a specified IBS EUROFloor material for an alternative IBS material, by the Contractor shall only be permitted with the Contract Administrator's written authorisation and shall be at no additional cost to the principal. Should any resultant extra work and/or redesign work be required to accommodate an alternative IBS material to satisfy design, performance, and compliance requirements, then the cost of these shall be borne by the Contractor.

Inspections & Reporting

BCA inspections of the works shall take place at each of the stages scheduled in the Building Consent. Confirm a written program to facilitate these inspections, including notification when each stage of the work is ready for inspection.

Carry out all necessary pre-installation and installation inspections for each area of the works.

Complete all necessary Pre and post Installation Checklists.

Complete all necessary Sign-Off Certificates before handing over completed work.

Quality Assurance

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of the works are carried out to the highest standard.

Defective Materials & Work

Should defective materials and/or work be found at any time before the final acceptance of the work, it shall be rejected. Rejected IBS EUROFloor, work shall be repaired and/or replaced to the satisfaction of the Contract Administrator, without delay and at no additional cost to the Principal.

2.3 IBS EUROFloor

Help Note:

For product information and technical advice please info@ibs.co.nz, or call 0800 367 759.

For technical information on products to attach to this project, please visit www.ibs.co.nz

SMARTSPEC