Plytech Joinery & Cabinetry

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 2
- Plytech Clicwall FR 5
- Plytech Prefinished Plywood Panel 8
- Plytech Unfinished Plywood Panel 14
- Plytech Non-Plywood Material 21
- Ancillary Components & Accessories 27
- Finish Coatings 31
- Co-operation 33
- Workmanship 33
- Delivery & Handling 34
- Preparation 35
- Manufacture & Installation 36
- Completion 37

Compliances 38

SWARTSPEC

1 Specification Details

Trade Sections: Joinery
Description:
Keywords: Joinery, Plytech Joinery & Cabinetry, kitchen joinery, bathroom joinery, commercial joinery, office joinery, prefinished plywood, plywood, unfinished plywood, plywood panels, plywood sheets,

2 Clauses

2.1 Scope

Help Note:
If in doubt about any aspect of your specification please email Plytech International Ltd at sales@plytech.co.nz, or call 0800 900 905.

For technical information on products to attach to this project, please visit https://productspec.co.nz/en/supplier/plytech

2.1.1 Scope

Manufacture and install Clicwall FR / custom-made joinery and cabinetry fittings and elements, as indicated on the design drawings and schedules, incorporating materials from the Plytech International Ltd range of Clicwall / 'Furniture' panel products specified herein, complete with all necessary components and accessories required for proper manufacture, assembly, installation, functionality and performance. All aspects of this work shall be in complete accordance with Plytech International Ltd technical literature (check www.plytech.co.nz, or email sales@plytech.co.nz, or call 0800 900 905 for the latest editions), other relevant product manufacturers' recommendations, and as shown on the design drawings.

No substitutions are permitted for materials and products specified herein and on the design drawings and schedules.

2.1.2 Extent of Work

The following is a list and/or general description of the extent of the Plytech Clicwall / Joinery & Cabinetry works, which are more specifically defined in the contract documents, required for the completion of the contract works:

2.2 Requirements

Help Note:
Clause options listed below are optional - as applicable, select only those options according to project requirements.

SMARTSPEC

If in doubt about any aspect of your specification please email Plytech International Ltd at sales@plytech.co.nz, or call 0800 900 905.

2.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

2.2.2 Warranty - Product

Plytech International Ltd Product Warranty - as applicable and according to warranty terms and conditions.

- For all Plytech materials used in the manufacture of factory-made custom joinery/cabinetry.
- Provide the warranty on the Plytech International Ltd standard warranty form.
- Commence the warranty no later than three days after delivery.

2.2.3 Warranty - Installation

Installer's Installation Warranty - according to warranty terms and conditions.

- 2 Years Workmanship Warranty for all factory-made custom joinery/cabinetry elements installed.
- Provide the Installation Warranty on the installer standard warranty form.
- Commence the warranty from the date of practical completion of the contract works.

2.2.4 Substitutions

Plytech Joinery & Cabinetry panel materials shall be as specified herein and as indicated on the design drawings. The substitution of the specified Plytech Joinery & Cabinetry panel materials for an alternative brand or material is not permitted under any circumstances.

The substitution of a specified Plytech panel material for an alternative Plytech panel material by the Contractor shall only be permitted with the Contract Administrator's written authorisation, and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate an alternative Plytech panel material to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor.

2.2.5 Shop Drawings

Before production commences, prepare and submit to the Contract Administrator for verification, preliminary Shop Drawings for each joinery/cabinetry element based on the design drawings.

Following Shop Drawing review, perform a Site Check when the installation areas are ready, and issue For Fabrication & Installation (FFI) Drawings, clearly identifying all inconsistencies between the FFI Drawings and Shop Drawings, for approval of the Contract Administrator before fabrication of joinery and cabinetry elements commences.

Shop drawings shall include, but not be limited to, the following aspects of the joinery/cabinetry design and installation:

- Fully dimensioned plans, elevations, and sections of all elements, identifying all components,