Plytech Pinetech Cavity System

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 3
- Plywood - Pinetech Cladding 4
- Cover Battens & Timber Mouldings 7
- Ancillary Components & Accessories 9
- Finish Coating 10
- Cavity Battens 10
- Cavity Base Closer 10
- Flashings 11
- Co-operation 13
- Workmanship 13
- Delivery & Handling 13
- Preparation 14
- Installation 15
- Fixing 18
- Completion 21

Compliances 22

SMARTSPEC

1 Specification Details

Trade Sections: Carpentry
Description:
Keywords: Carpentry, Plytech, Pinetech, cavity cladding, cavity system, plywood cladding, exterior plywood cladding, Plywood panels, plywood sheets

2 Clauses

2.1 Scope

Help Note:
This specification covers the Plytech Pinetech Cavity System, incorporating Pinetech exterior-grade plywood (to AS/NZS 2271) as cavity-based wall cladding installed over timber wall framing with a nominal 20mm drained cavity.

If in doubt about any aspect of your specification please email Plytech International Ltd at sales@plytech.co.nz, or call 0800 900 905.

For technical information on products to attach to this project, please visit https://productspec.co.nz/en/supplier/plytech

2.1.1 Scope

Supply and install Plytech Pinetech Cavity System, as specified herein, as exterior cladding to the locations identified on the drawings, complete with all system components and accessories required for proper installation and performance. All aspects of this work shall be in complete accordance with Plytech International Ltd technical literature (check www.plytech.co.nz, or email sales@plytech.co.nz, or call 0800 900 905 for the latest editions), other relevant product manufacturers' recommendations, and the New Zealand Building Code.

No substitutions are permitted for Plytech Pinetech Cavity System.

For the purpose of this specification, Plytech Pinetech Cavity System is referred to as 'Pinetech Cavity System'.

2.1.2 Extent of Work

The following is a list and/or general description of the extent of the Plytech Plywood Cladding works, which are more specifically defined in the contract documents, required for the completion of the contract works:

SMARTSPEC

2.2 Requirements

Help Note:
Clause options listed below are optional - as applicable, select only those options according to project requirements.

If in doubt about any aspect of your specification please email Plytech International Ltd at sales@plytech.co.nz, or call 0800 900 905.

2.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

2.2.2 Warranty - Product

Plytech International Ltd Product Warranty - as applicable and according to warranty terms and conditions.
- For Plytech plywood cladding materials.
- Provide the warranty on the Plytech International Ltd standard warranty form.
- Commence the warranty no later than three days after delivery.

2.2.3 Substitutions

Pinetech Cavity System materials shall be as specified herein and as indicated on the design drawings. The substitution of Plytech Pinetech Cavity System for an alternative brand, system or material is not permitted under any circumstances.

The substitution of a specified Plytech plywood material for an alternative Plytech plywood material by the Contractor shall only be permitted with the Contract Administrator's written authorisation, and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate an alternative Plytech plywood material to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor.

2.2.4 Samples

Submit a clearly identified, 300 x 300mm sample of the Pinetech Cavity System plywood material specified for assessment by the Contract Administrator - do not proceed until the sample has been approved.

2.2.5 Quality Assurance

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of the works are carried out to the highest standard.

Ensure that the installation and finishing of Pinetech Cavity System cladding comply in all respects with the approved design drawings and specifications, and Building Consent.

SMARTSPEC