FPS - Frame Protection System

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 2
- FPS - Frame Protection - Wall and Roof Underlay System 4
- Ancillary Components & Accessories 7
- Co-operation 13
- Workmanship 13
- Delivery & Handling 13
- Preparation 14
- Installation - FPS - Frame Protection System - Wall Underlay System 15
- Installation - FPS - Frame Protection System - Roof Underlay System 15
- Completion 15

Compliances 15

SMARTSPEC

1 Specification Details

Trade Sections: Carpentry, Roofing, Waterproofing
Description: Wall and Roof underlay system.
Keywords: wrap, roof wrap, membrane, underlay, roof underlay, wall wrap, Ventia Iron, Ventia, Ebuilt, Vibest, flashing tape

2 Clauses

2.1 Scope

2.1.1 Scope:

Supply and install FPS - Frame Protection System, as specified herein, to the locations and details shown on the design drawings, complete with all necessary components and accessories required for proper installation and performance. All aspects of this work shall comply with the NZ Building Code, related FPS - Building Frame Protection System technical literature and publications (check http://www.frameprotection.co.nz or email info@frameprotection.co.nz or call (0800) 723 426 for the latest editions), and other relevant product manufacturers recommendations.

Refer to CodeMark certificate CM70030 for product approval.

No substitutions are permitted for FPS - Frame Protection System.

For the purpose of this specification, the Wall and Roof Underlay System is referred to as 'FPS - Frame Protection System' and all 'FPS' associated technical literature and publications, including the Product Technical Statement, installation instructions and drawings, are collectively referred to as the 'technical literature'.

FPS - Frame Protection System is designed for residential and commercial buildings as a roof and wall underlay system.

Extent of work:

The following is a list and/or general description of the extent of the FPS - Frame Protection System works, which are more specifically defined in the contract documents, required for the completion of the contract works:

2.2 Requirements

2.2.1 Safety:

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

SMARTSPEC

2.2.2 Warranty:

FPS - Frame Protection System - Warranty - according to the warranty terms and conditions.

- Refer to FPS for the warranty period for nominated product.

- The warranty is based on FPS standard warranty terms and conditions.

- Commence the warranty from the date of original purchase.

2.2.3 Substitutions:

The Frame Protection System shall be as specified herein and on the design drawings. The substitution of the FPS - Frame Protection System for an alternative brand, system or product is not permitted under any circumstances.

The substitution of a specified FPS - Frame Protection System or component for an alternative FPS - Frame Protection System or component by the Contractor shall only be permitted with the Contract Administrator's written authorisation and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate an alternative FPS - Frame Protection System or component to satisfy design, performance, and compliance requirements, then the cost of these shall be borne by the Contractor.

2.2.4 Inspections & reporting:

BCA inspections shall take place at each of the stages as scheduled in the Building Consent. Confirm a written programme to facilitate these inspections, including notification when each stage of the work is ready for inspection.

Carry out all necessary pre-installation and installation inspections for each area of the works.

Complete all necessary Pre-Installation Checklists prior to installation, and all necessary Installation Checklists.

Complete all necessary Final Checklists and Installation Sign-Off Certificates before handing over completed work.

2.2.5 Quality assurance:

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of the work are carried out to the highest standard.

2.2.6 Defective materials & workmanship:

Should defective materials and/or work be found at any time before the final acceptance of the work, it shall be rejected. Rejected FPS - Frame Protection System materials and work shall be repaired and/or replaced to the satisfaction of the Contract Administrator without delay and at no additional cost to the Principal.

SMARTSPEC