Forté Millboard - Envello Cladding System

TABLE OF CONTENTS

Specification Details....2
Clauses....2
- Scope....2
- Requirements....2
- Forté Millboard - Envello Cladding....4
- Ancillary Components & accessories....6
- Co-operation....7
- Workmanship....7
- Delivery & Handling....7
- Preparation....8
- Installation....9
- Fixing....10
- Completion....10

Compliances....11

SWARTSPEC

1 Specification Details

Trade Sections: Carpentry, Cladding & PreCladding
Description: External cladding system
Keywords: Forte, forte, Forte cladding, Millboard cladding board, external cladding, composite cladding, pre-finished cladding, vertical cladding, Envello.

2 Clauses

2.1 Scope

Help Note:
For technical advice and specification guidance, contact Forté Ltd on 0508 356677

2.1.1 Scope:

Supply and install Forte Millboard Envello Cladding System, as specified herein, to the locations and details shown on the design drawings, complete with all necessary components and accessories required for proper installation and performance. All aspects of this work shall comply with the NZ Building Code, related Forte Millboard Envello Cladding System 'Technical literature' and publications

(check http://forte.co.nz, or email camilla@forte.co.nz, or call 0508 356677 for the latest editions), and other relevant product manufacturers' recommendations.

No substitutions are permitted for Forte Millboard Envello Cladding System.

For the purpose of this specification, the 'Cladding System' is referred to as 'Forte Millboard Envello Cladding System' and all 'Forte' associated technical literature and publications, including the Product Technical Statement, installation instructions and drawings, are collectively referred to as the 'Technical literature'.

Forte Millboard Envello Cladding System is designed for residential and commercial buildings as an external cladding system.

2.1.2 Extent of Work:

The following is a list and general description of the extent of the Forte Millboard Envello Cladding System works, which are more specifically defined in the contract documents, required for the completion of the contract works:

2.2 Requirements

2.2.1 Safety:

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

2.2.2 Warranty:

Millboard Envello Cladding System Warranty - according to the warranty conditions.

- 15 Years' Warranty for all Millboard Envello Cladding Systems installed.
- Provide this warranty on the manufacturer's standard warranty form.
- Commence the warranty from the date of practical completion of the contract works.

2.2.3 Substitutions:

The Forte Millboard Envello Cladding System shall be as specified herein and on the design drawings. The substitution of the Forte Millboard Envello Cladding System for an alternative brand, system or product is not permitted under any circumstances.

The substitution of a specified Forte Millboard Envello Cladding System or component for an alternative Forte Millboard Envello Cladding System or component by the Contractor shall only be permitted with the Contract Administrator's written authorisation and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate an

SMARTSPEC

alternative Forte Millboard Envello Cladding System or component to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor.

2.2.4 Samples:

Submit a clearly identified full-size sample of the specified Millboard Envello Cladding board and colour, for signed approval by the Contract Administrator - do not proceed until the samples have been approved.

Where a colour has not been specified, submit a clearly identified sample of each colour for the range specified, for colour selection and signed approval by the Contract Administrator.

2.2.5 Producer statement (PS3):

The Forte Millboard Envello Cladding System installer shall furnish a fully completed PS3 Producer Statement (Construction) at time of application for Code Compliance Certificate. The Producer Statement shall accurately reflect the scope of the installation of the Forte Millboard Envello Cladding System in accordance with the consented drawings and specifications.

2.2.6 Inspection & Reporting:

BCA inspections shall take place at each of the stages as scheduled in the Building Consent. Confirm a written programme to facilitate these inspections, including notification when each stage of the work is ready for inspection.

Carry out all necessary pre-installation and installation inspections for each area of the works.

Complete all necessary Pre-Installation Checklists prior to installation, and all necessary Installation Checklists.

Complete all necessary Final Checklists and Installation Sign-Off Certificates before handing over completed work.

2.2.7 Quality Assurance:

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of the works are carried out to the highest standard.

2.2.8 Defective materials & workmanship:

Should defective materials and/or work be found at any time before the final acceptance of the work, it shall be rejected. Rejected Forte Millboard Envello Cladding System materials and work shall be repaired and/or replaced to the satisfaction of the Contract Administrator without delay and at no additional cost to the Principal.

SMARTSPEC