Forté Alor Cabinetry & Veneer Panels

TABLE OF CONTENTS

Specification Details....2
Clauses....2
- Scope....2
- Requirements....3
- Alor Cabinetry & Veneer Panels....4
- Co-operation....11
- Workmanship....11
- Delivery, Handling & Preparation....12
- Installation....12
- Completion....12

Compliances....13

1 Specification Details

Trade Sections: Carpentry, Internal Doors & Joinery
Description: Forté Alor Cabinetry & Veneer Panels, cabinetry, veneer panels, timber veneer panels, wood veneer panels, decorative veneer panels, cabinetry panels, interior cabinetry, timber cabinetry, wood cabinetry, cabinet linings, wall veneer panels, ceiling veneer panels, interior wall panels, interior ceiling panels, timber panels, wood panels, wooden panels, decorative wall panels, decorative ceiling panels, architectural panels, prefinished panels, veneer sheet panels, interior finishes, decorative finishes, timber finishes, wood finishes, wall linings, ceiling linings, interior linings, feature walls, feature ceilings, joinery panels, architectural joinery, interior joinery, timber veneer finishes, natural timber veneer, engineered wood panels, panel systems, cabinetry finishes.
Keywords:

2 Clauses

2.1 Scope

Help Note:
For technical information on products to attach to this project, please visit Forté.co.nz

Additonal information can be found at Alor | Forté NZ

SWARTSPEC

Engineered veneer panels for cabinetry and interior wall linings.

2.1.1 Scope

Supply and install Forté Alor Cabinetry and Veneer Panels, as specified herein, to the locations, layout and details shown on the drawings, complete with all components and accessories required for proper installation. All aspects of this work shall be carried out in accordance with Forté technical literature and installation requirements (refer to www.forte.co.nz, email info@forte.co.nz, or call 0508 35 66 77 for the latest information), along with all relevant substrate and product manufacturer recommendations.

No substitutions are permitted for Forté Alor Cabinetry and Veneer Panels.

2.1.2 Extent of Work

The following is a list and general description of the extent of the Forté Interior Panelling works, which are more specifically defined in the contract documents, required for the completion of the contract works:

2.2 Requirements

Help Note:
Clause options listed below are optional - as applicable, select only those options according to project requirements.

For technical advice and specification guidance, contact Forté on 0800 445 494.

2.2.1 Safety

Comply with the Health and Safety at Work (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

2.2.2 Warranty, Product

Forté Alor Cabinetry & Veneer Panels — provide and install in accordance with Forté Flooring Ltd requirements and recommendations.

- For all Forté Alor Cabinetry & Veneer Panel systems supplied by Forté Flooring Ltd.
- Provide the Product Warranty on the Forté Flooring Ltd standard warranty form.
- Commence the warranty from the date of practical completion of the contract works.

2.2.3 Substitutions

Forté Alor Cabinetry & Veneer Panels shall be as specified herein and as indicated on the design drawings. The substitution of Forté Flooring Ltd supplied Forté Alor Cabinetry & Veneer Panels with alternative products or materials is not permitted under any circumstances.

SMARTSPEC

The substitution of a specified Forté Alor Cabinetry & Veneer Panel product with an alternative Forté Flooring Ltd product by the Contractor shall only be permitted with the Contract Administrator's written authorisation, and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate alternative Forté Alor Cabinetry & Veneer Panel products to satisfy design, performance, and compliance requirements, the cost of such work shall be borne by the Contractor.

2.2.4 Samples

Submit a clearly identified full-size sample of each wall and/or ceiling covering range and colour specified, for signed approval by the Contract Administrator - do not proceed until the samples have been approved.
Where a colour has not been specified, submit a clearly identified sample of each colour for the range specified, for colour selection and signed approval by the Contract Administrator.

2.2.5 Quality Assurance

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of the works are carried out to the highest standard.

2.2.6 Inspection & Reporting

Carry out all necessary pre-installation, installation and sign-off inspections of the works for each area of work in accordance with Forté Flooring Ltd requirements and industry best-practice recommendations.
Complete all necessary Pre-Installation and Installation Checklists.
Complete all necessary Sign-Off Certificates before handing over completed work.

2.2.7 Defective Materials & Work

Should defective materials and/or work be found at any time before final acceptance of the work, it shall be rejected. Rejected Forté Alor Cabinetry & Veneer Panel work shall be repaired and/or replaced to the satisfaction of the Contract Administrator without delay and at no additional cost to the Principal.

2.2.8 Reserve Material

On completion of the installation works, supply and deliver to the Owner/Principal the specified quantity of unopened packs for each Forté Alor Cabinetry & Veneer Panel product installed.

Quantity:

2.3 Alor Cabinetry & Veneer Panels

Help Note:
Please note: Ember is the only American Walnut colourway. All other colours are European Oak. Each colour is available as a 19mm full panel (1F1B) in two lengths, and a 7mm skin panel (1FAB).

SMARTSPEC