Plymasters Joinery & Cabinetry

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 2
- Plymasters Timber Veneer Panels 4
- Plymasters Timber Veneer Panels – Prefinished 6
- Plymasters Joinery & Furniture Plywood 8
- Plymasters Wall & Ceiling Linings 32
- Plymasters – Marine Plywood 36
- Plymasters Laminate Panels 48
- Ancillary Components & Accessories 54
- Finish Coatings 58
- Co-operation 59
- Workmanship 59
- Delivery & Handling 60
- Preparation 61
- Completion 62

Compliances 63

SMARTSPEC

1 Specification Details

Trade Sections: Joinery
Description: Joinery & Cabinetry
Keywords: Plymasters, Joinery, Cabinetry, Plywood, Timber Veneer Panels, Marine Plywood, Plywood, Oak, Birch, MDF, Furnier American Walnut, Walnut, Laminate Panels, Joinery & Furniture plywood, Marine Plywood, Timber Veneer Panels.

2 Clauses

2.1 Scope

Help Note:
For technical enquiries contact Plymasters on 0800344112 or e-mail sales@plymasters.co.nz or head to the website www.plymaster.co.nz

For technical information on products to attach to this project, please visit https://productspec.co.nz/en/supplier/plymasters

2.1.1 Scope

The following is a list and/or general description of the extent of the Plymasters Joinery & Cabinetry works, which are more specifically defined in the contract documents, required for the completion of the contract works:
Manufacture and install custom-made joinery and cabinetry fittings and elements, as indicated on the design drawings and schedules, incorporating materials from the Plymasters range of 'Joinery & Furniture Ply' panels, “Laminate” Panels, “Timber Veneer” panels & “Prefinished Veneer” panel products specified herein, complete with all necessary components and accessories required for proper manufacture, assembly, installation, functionality and performance. All aspects of this work shall be in complete accordance with Plymasters technical literature (check https://plymasters.co.nz/ply-products/, or email sales@plymasters.co.nz, or call 0800 344 112 for the latest editions), other relevant product manufacturers' recommendations, and as shown on the design drawings.
No substitutions are permitted for materials and products specified herein and on the design drawings and schedules.

2.2 Requirements

2.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes

of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance

2.2.2 Warranty - Product

Plymasters Product Warranty - as applicable and according to warranty terms and conditions.
- For all Plymasters materials used in the manufacture of factory-made custom joinery/cabinetry.
- Provide the warranty on the Plymasters standard warranty form.
- Commence the warranty no later than three days after delivery.

2.2.3 Warranty - Installation

Installer's Installation Warranty - according to warranty terms and conditions.
- 1 Years Workmanship Warranty for all factory-made custom joinery/cabinetry elements installed.
- Provide the Installation Warranty on the installer standard warranty form.
- Commence the warranty from the date of practical completion of the contract works.

2.2.4 Substitutions

Plymasters Joinery & Cabinetry panel materials shall be as specified herein and as indicated on the design drawings. The substitution of the specified Plymasters Joinery & Cabinetry panel materials for an alternative brand or material is NOT permitted under any circumstances.
The substitution of a specified Plymasters panel material for an alternative Plymasters panel material by the Contractor shall only be permitted with the Contract Administrator's written authorisation, and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate an alternative Plymasters panel material to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor

2.2.5 Shop Drawings

Before production commences, prepare and submit to the Contract Administrator for verification, preliminary Shop Drawings for each joinery/cabinetry element based on the design drawings.
Following Shop Drawing review, perform a Site Check when the installation areas are ready, and issue For Fabrication & Installation (FFI) Drawings, clearly identifying all inconsistencies between the FFI Drawings and Shop Drawings, for approval of the Contract Administrator before fabrication of joinery and cabinetry elements commences.
Shop drawings shall include, but not be limited to, the following aspects of the joinery/cabinetry design and installation:
- Fully dimensioned plans, elevations, and sections of all elements, identifying all components, materials, hardware, door swings, appliances, etc.
- Complete details showing joinery/cabinetry form, components, and installation details - including with adjacent work.
- Dimensions of all typical elements, and special sizes and shapes.
- Positions of joinery/cabinetry-mounted services, including electrical switches, power outlets, light fittings; water supplies, waste outlets, etc.
- Co-ordination requirements with other work and trades - where required.
- A schedule of all materials, finishes, componentry, hardware, fixings, sealants, etc..