PSP ClearVue Roofing System

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 3
- ClearVue System 4
- ClearVue Glazing Panel 5
- ClearVue Aluminium Extrusions 6
- Aluminium Finish 6
- Ancillary Components & Accessories 7
- Co-operation 9
- Workmanship 9
- Delivery & Handling 10
- Preparation 10
- Installation 11
- Completion 15

Compliances 15

SMARTSPEC

1 Specification Details

Trade Sections: Roofing
Description:
Keywords: PSP, PSP ClearVue Roofing System, clearvue, roofs, roofing, rooves, roof, clear vue, glazing bar system, span bar, timber rafter system

2 Clauses

2.1 Scope

Help Note:
For technical advice and specification guidance, email PSP Ltd at info@psp.co.nz or call 0800 786 883.

For technical information on products to attach to this project, please visit https://productspec.co.nz/en/supplier/psp limited

2.1.1 Scope

Supply and install PSP ClearVue Roofing System, as specified herein, to the locations indicated on the design drawings, complete with all necessary components and accessories required for proper installation and performance. All aspects of this work shall be in complete accordance with the PSP ClearVue Roofing System technical literature and details (check www.clearvue.co.nz, email info@psp.co.nz, or call 0800 786 883 for the latest editions), BRANZ Appraisal No.887, and other relevant product manufacturers' recommendations.

No substitutions are permitted for PSP ClearVue Roofing System.

For the purpose of this specification, all related PSP ClearVue Roofing System technical literature and detail drawings and BRANZ Appraisal is referred to as the 'Technical Literature'.

The ClearVue Roofing System is an exterior roofing system for use in NZS 3604 wind Zones up to and including Extra High, and with a minimum roof pitch of 3° (5° recommended) and maximum roof pitch of 30°.

2.1.2 Extent of Work

The following is a list and/or general description of the extent of the PSP ClearVue Roofing System works, which are more specifically defined in the contract documents, required for the completion of the contract works:

SMARTSPEC

2.2 Requirements

Help Note:
Clause options listed below are optional - as applicable, select only those options according to project requirements.

For technical advice and specification guidance, email PSP Ltd at info@psp.co.nz or call 0800 786 883.

2.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

2.2.2 Warranty - Material

PSP Ltd Material Warranty - according to the warranty terms and conditions.
- 15-Year Warranty for defects in the material and manufacture of the specified products.
- Provide this warranty on the manufacturer's standard warranty form.
- Commence the warranty from the date of purchase.

2.2.3 Warranty - Installation

Installation Warranty.
- 5 Years for Workmanship.
- Provide this warranty on the ClearVue Roofing System installer's standard warranty form.
- Commence the warranty from the date of practical completion of the roof.

Include a copy of the PSP Ltd maintenance requirements with the Installation Warranty.

2.2.4 Substitutions

The PSP ClearVue Roofing System shall be as specified herein and on the design drawings. The substitution of the ClearVue Roofing System for an alternative brand, system or material is not permitted under any circumstances.

The substitution of a specified ClearVue system or product for an alternative ClearVue system or product by the Contractor shall only be permitted with the Contract Administrator's written authorisation and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate an alternative ClearVue system or product to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor.

2.2.5 Inspections & Reporting

BCA inspections shall take place at each of the stages as scheduled in the Building Consent. Confirm a written programme to facilitate these inspections, including notification when each stage of the work is ready for inspection.

SMARTSPEC