Resene Construction Systems
Plaster Cladding

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- General 2
- Workmanship 3
- Work 3
- Preparation 4
- Wall Structure/Substrate 4
- Cavity Battens 6
- Installation 6
- Mesh Coat 10
- Finish 12
- Protective Finish Coat 14

Compliances 17

SWARTSPEC

1 Specification Details

Trade Sections: Plasterwork
Description:
Keywords: Plasterwork, Rockcote Resene, plaster, plastering, plaster cladding, plastered cladding, cladding, plaster systems, plaster cladding systems, plastered cladding systems, cladding systems, wall cladding plaster, plastered wall cladding systems, exterior wall cladding systems, plastered exterior wall cladding systems, plastered walls, wall plaster, plastered facade systems, facade plaster systems, plastered polystyrene cladding, plastered EPS cladding, plastered XPS cladding, plastered Integra cladding, plastered lightweight concrete cladding, plastered light-weight concrete cladding, plastered light weight concrete cladding, plastered LWC cladding, plastered precast concrete panels, plastered concrete, plastered AAC, plastered concrete block, plastered concrete blockwork, plastered fibre cement sheet, plastered fibre-cement sheet, plastered masonry block, Rockcote Quick Render, Rockcote PM 100 Quick Render, Rockcote Literock Solid Render, Rockcote Renderprime, Rockcote Coloured Texture, Rockcote Armour, Integra

2 Clauses

2.1 Scope

Help Note:
For technical information on products to attach to this project, please visit
https://productspec.co.nz/en/supplier/resene construction systems

2.1.1 Scope

All of the wall surfaces identified for Rockcote on the drawings, together with all associated flashings, reveals finishing and other details. Note that no substitutions are permissible for any of the products specified herein.

2.2 General

2.2.1 General

All materials and workmanship incorporated into the house construction by this subcontract shall be such as to qualify in every detail and respect for the Rockcote 15 year Product Performance Warranty and the Licensed Rockcote Plasterers 5 year Workmanship Warranty.

If the Cladding Plasterer considers that general conditions of previous work is unsatisfactory to ensure a proper finish for the cladding work required they shall give immediate notice to the Contractor or Designer as appropriate and shall not proceed until necessary improvements have been made. Failing such notice the Cladding Plasterer will not be relieved of the responsibility for a poor finish due to such unsatisfactory condition.

SMARTSPEC

(and)
'The Contractor and Subcontractors affected shall be jointly and severally responsible for completion of the whole of the works in a completely watertight condition and shall therefore examine all details to be satisfied that this condition can be achieved. If any detail is considered unsatisfactory the Designer shall be immediately notified and they will then either interpret the detail to the Contractor's satisfaction, or accept responsibility for watertightness at the points in question, always assuming reasonable workmanship.'

2.3 Workmanship

2.3.1 Workmanship

All work shall be carried out by experienced and skilled PPCS (Proprietary Plaster Cladding Systems) Registered Tradesmen licensed to apply Rockcote Systems exterior cladding renders, and be in accordance with best and latest trade practice. Ensure that all plant and tools are kept clean and free from earlier mixes.

Apply all materials and install all Rockcote and Resene sealers, renders and protective coatings in strict accordance with manufacturer's recommendations.

Carefully proportion each batch and thoroughly mix. No re-tempering of any partially set or dried material. Observe Rockcote specification requirements with regard working in direct sun and protecting work from rain or frost for 24 hours or until cured.

Arrange plastering sequence to avoid conspicuous join marks or badly set out joins in large surfaces. Properly cure all plaster to prevent shrinkage or druminess. Leave all plastered surfaces clean, sound, smooth, even and with a true finish, and free from blemishes of any kind.

2.4 Work

2.4.1 Work

Arrange for all appropriate or required inspections by Rockcote Systems registered PPCS assessors to qualify for their 15 year warranty.

Submit a clearly identified 300 x 300mm sample of the selected texture finish and colour for signed approval of the Designer or Owner as appropriate, and do not proceed until this is returned.

Ensure that the work of other trades does not reduce the cladding to ground, deck or roof clearances that are required by the Code.

Clean up thoroughly on completion, and provide the producer statement and appropriate warranties to the main contractor. Provide on-going maintenance instructions to ensure that NZBC Durability requirements are met.

SMARTSPEC