Warmup Wetroom System

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Undertile Waterproofing Membrane 2
- Marmox™ Shower Base 2
- Tranquility™ Channel Drains 3
- Glass Doors & Screens 4
- Undertile Heating 4
- Warmup™ Thermostats 4
- Tiling 5
- Co-operation 5
- Workmanship 5
- Preparation 6
- Installation 7
- Completion 8

Compliances 8

SMARTSPEC

1 Specification Details

Trade Sections: Waterproofing
Description:
Keywords:

2 Clauses

2.1 Scope

2.1.1 Warmup™ Waterproofing System

Supply and install the specified Warmup™ Waterproofing System components to the locations identified on the drawings, complete with accessories. All aspects of this work shall be in complete accordance with Warmup product technical literature (check www.warmup.co.nz or call 0800 WARMUP (927 687) for the latest editions), associated Warmup BRANZ Appraisals, other relevant product manufacturers' recommendations, and as shown in the drawings.

No substitutions are permitted for the Warmup™ Waterproofing System and components specified on the approved plans.

2.2 Undertile Waterproofing Membrane

Help Note:
Warmup™ WPM750 Undertile Butynol

- Refer to Waterproofing Section for Ardex WPM 750 Undertile Membrane requirements and substrate preparation.

Installed Location:

2.2.1 Undertile Waterproofing Membrane

Warmup 750 Undertile Waterproof Membrane

Warmup™ 750 Undertile Waterproofing Membrane

· Refer to Warmup Technical Literature for Warmup 750 Undertile Membrane requirements and substrate preparation.

Installed Location: Internal Wet Areas

2.3 Marmox™ Shower Base

2.3.1 Marmox™ Shower Base

Marmox™ preformed waterproof shower base available in different sizes

SMARTSPEC

Shower trays are cut to suit the application, with preformed falls to the selected waste of 1:50 for point drains and 1:100 for channel drains.

Installed Location: Internal Wet Areas

2.4 Tranquility™ Channel Drains

2.4.1 Channel Drain - Solid Brushed Stainless Steel

Tranquillity™ 316 stainless steel drain with Stainless Steel cover. Ensure waterproofing, sanitary plumbing work with appropriate flange clamp waste and shower base fitment has been completed and tested prior to installation. Check for any defects and report immediately if identified.

800mm long x 69mm wide x 21mm deep with 45mm diameter centre outlet.

Installed Location:

2.4.2 Channel Drain - Linear Stainless Steel

Tranquillity ™ 316 stainless steel drain with Linear Stainless Steel cover. Ensure waterproofing, sanitary plumbing work with appropriate flange clamp waste and shower base fitment has been completed and tested prior to installation. Check for any defects and report immediately if identified.

800mm long x 69mm wide x 21mm deep with 45mm diameter centre outlet

Installed Location:

2.4.3 Channel Drain - Mesh Stainless Steel

Tranquillity™ 316 stainless steel drain with Mesh Stainless Steel cover. Ensure waterproofing, sanitary plumbing work with appropriate flange clamp waste and shower base fitment has been completed and tested prior to installation. Check for any defects and report immediately if identified.

800mm long x 69mm wide x 21mm deep with 45mm diameter centre outlet

Installed Location:

2.4.4 Channel Drain - Tile Insert

Tranquillity™ 316 stainless steel drain with Tile Insert cover. Ensure waterproofing, sanitary plumbing work with appropriate flange clamp waste and shower base fitment has been completed and tested prior to installation. Check for any defects and report immediately if identified.

Fix selected tile to cover the tray with tile adhesive.

800mm long x 69mm wide x 21mm deep with 45mm diameter centre outlet

Installed Location:

Insert tile(10mm):

SMARTSPEC