James Hardie Hardie™ Glaze Lining

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Co-operation 3
- Preparation 3
- Flexible Sealant 4
- Adhesive Sealant 5
- Workmanship 6
- Delivery & Handling 6
- Installation 6
- Fixings 7
- Completion 8

Compliances 8

SWARTSPEC

1 Specification Details

Trade Sections: Carpentry
Description:
Keywords: Carpentry, James Hardie, Hardies, fibre cement, fibre-cement, lining, linings, internal linings, interior linings, wall lining, wall linings, internal wall lining, ceiling lining, ceiling linings, interior walls and ceilings, interior walls & ceilings, wall and ceiling linings, wall & ceiling linings, fibre cement lining, fibre-cement lining, fibre cement sheet lining, fibre-cement sheet lining, fibre cement sheets, fibre-cement sheets, lining panels, lining sheets, sheet lining, panel lining, fibre-cement panel, fibre-cement panels, fibre-cement panelling, fibre cement panel, fibre cement panels, fibre cement panelling, cellulose cement sheet, pre-finished fibre cement, pre-finished fibre-cement, pre-finished lining, pre-finished linings, pre-finished wall linings, pre-finished ceiling lining, pre-finished wall and ceiling linings, wet area lining, wet-area lining, HarideGlaze, Smooth Lining, HardieGlaze Tile Lining, HardieGlaze Tile Lining, Listello, HardieGlaze Premium Lining,

2 Clauses

2.1 Scope

Help Note:
James Hardie HardieGlaze Lining are pre-finished with a polyurethane coating, and are manufactured in different widths, lengths, thicknesses, and surface appearances. They can be direct-fixed to framing, or installed over over fibre cement or plasterboard, to interior walls and ceilings only. The sheets are suitable for timber-framed buildings that fall within the scope of NZBC E3/AS1. Refer to the James Hardie HardieGlaze Lining Installation Manual for further information.

For technical information on products to attach to this project, please visit productspec.co.nz/en/supplier/james%20hardie.

2.1.1 Walls, Hardie™ Glaze Lining 4.5mm

Supply and install James Hardie Hardie™ Glaze Lining 4.5mm sheets as a pre-finished fibre-cement sheet lining material to the walls identified on the drawings, complete with all accessories. All aspects of this work shall be in complete accordance with the Hardie™ Glaze Lining Installation Manual by James Hardie (check www.jameshardie.co.nz, or call 0800 808 868 for the latest edition) and other relevant product manufacturers' recommendations.

2.1.2 Walls, Hardie™ Glaze Tile Lining 6mm

Supply and install James Hardie Hardie™ Glaze Tile Lining 6mm sheets as a pre-finished fibre-cement sheet lining material to the walls identified on the drawings, complete with all accessories. All aspects of this work shall be in complete accordance with the Hardie™ Glaze Lining Installation Manual by

SMARTSPEC

James Hardie (check www.jameshardie.co.nz, or call 0800 808 868 for the latest edition) and other relevant product manufacturers' recommendations.

2.1.3 Walls, Hardie™ Glaze Lining 6mm

Supply and install James Hardie Hardie™ Glaze Lining 6mm sheets as a pre-finished fibre-cement sheet lining material to the walls identified on the drawings, complete with all accessories. All aspects of this work shall be in complete accordance with the Hardie™ Glaze Lining Installation Manual by James Hardie (check www.jameshardie.co.nz, or call 0800 808 868 for the latest edition) and other relevant product manufacturers' recommendations.

2.1.4 Ceilings, Hardie™ Glaze Smooth Lining 4.5mm

Supply and install James Hardie Hardie™ Glaze Lining Smooth 4.5mm sheets as a pre-finished fibre-cement sheet lining material to the ceilings identified on the drawings, complete with all accessories. All aspects of this work shall be in complete accordance with the Hardie™ Glaze Lining Installation Manual by James Hardie (check www.jameshardie.co.nz, or call 0800 808 868 for the latest edition) and other relevant product manufacturers' recommendations.

2.1.5 Ceilings, Hardie™ Glaze Lining 6mm

Supply and install James Hardie Hardie™ Glaze Lining 6mm sheets as a pre-finished fibre-cement sheet lining material to the ceilings identified on the drawings, complete with all accessories. All aspects of this work shall be in complete accordance with the Hardie™ Glaze Lining Installation Manual by James Hardie (check www.jameshardie.co.nz, or call 0800 808 868 for the latest edition) and other relevant product manufacturers' recommendations.

2.2 Co-operation

2.2.1 Co-operation

Co-ordinate with other trades to ensure that appropriate clearances are allowed from adjacent internal linings, and bathroom fixture products and associated services, etc, that the sheets correctly allow for door and window installation, and that services penetrations are correctly handled to maintain full watertightness and sheet integrity. Ensure that other trades are aware of the James Hardie Safe Working Practices.

2.3 Preparation

2.3.1 General Preparation

Check that the timber framing elements are in accordance with NZS 3604, or in accordance with NZS 3603 and AS/NZS 1170 for specific design, and in accordance with James Hardie requirements. Framing shall be plumb and in true alignment, complete and suitable for the sheets, and maximum moisture content as per NZS 3602. Ensure that the framing is true in line with no projections due to structural and bracing bracketry etc. Ensure that the bottom plate hold-downs are correctly installed.

Check that the building has been completely finished to all penetrations including doors, windows, services, etc so that the sheets can be installed without being affected by any weather conditions. Check junctions to all other building elements and ensure that all necessary works have been