Specialized Caviteclad EIFS Cladding System

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 3
- Caviteclad System 5
- Caviteclad Plaster System 5
- Components & Accessories 6
- Co-operation 8
- Workmanship 8
- Delivery & Handling 9
- Preparation 10
- Installation 12
- Fixing 15
- Plaster System - Base Coat 20
- Plaster System - Finish Coat 21
- Exterior Paint System 24
- Completion 25

Compliances 25

SMARTSPEC

1 Specification Details

Trade Sections: Plasterwork
Description:
Keywords: Plasterwork, Specialized Construction Products, Specialized Caviteclad EIFS Cladding System, EIFS, polystyrene cladding, plastered cladding, plastered polystyrene cladding, insulated cladding, exterior insulation finish system, plastering, plaster finish, insulated cladding, EPS cladding, Caviteclad 50mm EIFS Cladding System, Caviteclad Thermashell 75mm EIFS Cladding System, cement-based plaster system, acrylic-based plaster system, cement/acrylic plaster system, Powerflex plaster, fine spray texture plaster, float finish plaster, spanish plaster, stucco texture plaster, Gronopor Fine 1.0mm acrylic texture, Granopor Top 1.5mm acrylic texture, Plastershield paint system,

2 Clauses

2.1 Scope

Help Note:
This section covers the supply and installation and finishing of the Caviteclad Cladding EIFS System from Specialized Construction Products (SCP), including the Caviteclad 50mm EIFS Cladding System and the Caviteclad Thermashell 75mm EIFS Cladding System.

For technical advice and specification guidance, email Specialized Construction Products at info@specialized.co.nz or call 0800 0800 79.

For technical information on products to attach to this project, please visit https://productspec.co.nz/en/supplier/specialized construction products

2.1.1 Scope

Supply and install Specialized Caviteclad EIFS Cladding System, as specified herein, to the locations identified on the design drawings, complete with all system components and accessories required for proper installation and performance. All aspects of this work shall be in complete accordance with the Specialized Construction Products (SCP) technical literature, including the Caviteclad Specification and Caviteclad Installation Guide and detail drawings (check www.specialized.co.nz, or email info@specialized.co.nz, or call 0800 0800 79 for the latest editions), BRANZ Appraisal No.510 (2019), and other relevant product manufacturers' recommendations.

No substitutions are permitted for Specialized Caviteclad EIFS Cladding System.

For the purpose of this specification, the Specialized Caviteclad EIFS Cladding System is referred to as 'Caviteclad Cladding', and Specialized Construction Products is referred to as 'SCP'. All associated SCP technical literature, including the Caviteclad Installation Guide and Caviteclad Specification and detail drawings, and the BRANZ Appraisal, is collectively referred to as the 'Technical Literature'.

SMARTSPEC

All PVC flashings, fibreglass mesh, resin, fixings and plaster components used for the Caviteclad Cladding system must be supplied by SCP or one of its certified distributors.

The Caviteclad Cladding plaster system must be finished with Dulux AcraTex 955 AcraSheild Advance100% acrylic paint system in accordance with SCP paint specifications.

2.1.2 Extent of Work

The following is a list and/or general description of the extent of the Caviteclad Cladding works, which are more specifically defined in the contract documents, required for the completion of the contract works:

2.2 Requirements

Help Note:
Designer - Clause options listed below are optional - as applicable, select only those options according to project requirements.

For technical advice and specification guidance, email Specialized Construction Products at info@specialized.co.nz or call 0800 0800 79.

2.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

2.2.2 Warranty - System

SCP System Warranty - according to the warranty terms and conditions.

- 15-Year Warranty for the failure of the Caviteclad Cladding system under normal environmental and use conditions.
- Provide this warranty on the manufacturer's standard warranty form.
- Commence the warranty from the date of practical completion of the works.

2.2.3 Warranty - Workmanship

Workmanship Warranty.

- 5-Year Warranty for workmanship and execution of the Caviteclad Cladding.
- Commence the warranty from the date of practical completion of the contract works.

2.2.4 Substitutions

The Caviteclad Cladding shall be as specified herein and on the design drawings. The substitution of Caviteclad Cladding for an alternative brand or cladding system or material is not permitted under any circumstances.

SMARTSPEC