JSC Interior Panelling

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 2
- Timber Species 4
- JSC Standard TG&V Panelling Profiles 5
- JSC Architectural Panelling Profiles - Matching JSC Rusticated Weatherboards. 7
- JSC Architectural Panelling Profiles - Matching JSC Vertical Shiplap Weatherboards 8
- Co-operation 10
- Workmanship 10
- Delivery, Handling & Preparation 10
- Fixing 11
- Installation 13
- Completion 13

Compliances 14

SMARTSPEC

1 Specification Details

Trade Sections: Carpentry
Description: Wall and Ceil panel and sarking.
Keywords: Western Red Cedar Alaskan Yellow Cedar Western Hemlock Iroko Tasmanian Oak American White Oak TMT Taxon TMT Taiga. Lunawood

2 Clauses

2.1 Scope

Help Note:
For technical information on products to attach to this project, please visit www.jsc.co.nz or call Auckland 094122800 or Christchurch 03348976

2.1.1 Scope

Supply and install the selected JSC Interior Panelling to the walls identified on the drawings, complete with all accessories and trim. Profile/s machined to JSC Panelling & Sarking Profiles.
All aspects of this work shall be in complete accordance with JSC's specifications and installation documentation requirements (email tasis@jsc.co.nz, or call 09 412 2800 for the latest editions), other relevant manufacturers' recommendations, and as shown on the drawings.
Durability shall be to NZ3602 and NZBC E3/AS1, and material compatibility through all cladding elements shall comply with E3/AS1 E3.3.4 and E3.3.5.

JSC producer sustainability certifications are downloadable from www.jsc.co.nz.

No substitutions are permitted for JSC Internal Panelling System.

2.2 Requirements

Help Note:
For technical information on products to attach to this project, please visit www.jsc.co.nz or call Auckland 094122800 or Christchurch 03348976

2.2.1 Safety

Safety
Comply with the Health and Safety at Work (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe Mahi Haumaru Aotearoa (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

2.2.2 Warranty, Product

Warranty, Product
JSC Product Warranty - according to the warranty conditions. As per the NZ Building Performance

SMARTSPEC

NZS3602.

- For all Wall and Ceiling Coverings supplied by JSC.
- Provide the Product Warranty on the JSC standard warranty form.
- Commence the warranty from the date of practical completion of the contract works.

2.2.3 Substitutions

Substitutions

JSC Interior Panelling shall be as specified herein and as indicated on the design drawings. The substitution of JSC supplied JSC Interior Panelling an alternative material is not permitted under any circumstances.

The substitution of a specified JSC Panelling product for an alternative JSC product, by the Contractor, shall only be permitted with the Contract Administrator's written authorisation, and shall be at no additional cost to the principal. Should any resultant extra work and/or redesign work be required to accommodate alternative JSC Interior Panelling products to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor.

2.2.4 Samples

Samples

Submit a clearly identified full-size sample of each wall and/or ceiling covering range and colour specified, for signed approval by the Contract Administrator - do not proceed until the samples have been approved.

Where a colour has not been specified, submit a clearly identified sample of each colour for the range specified, for colour selection and signed approval by the Contract Administrator.

2.2.5 Quality Assurance

Quality Assurance

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of the works are carried out to the highest standard.

2.2.6 Inspection & Reporting

Inspection & Reporting

Carry out all necessary pre-installation, installation and sign-off inspections of the works for each area of work in accordance with JSC requirements and industry best-practice recommendations.

Complete all necessary Pre-Installation and Installation Checklists.

Complete all necessary Sign-Off Certificates before handing over completed work.

2.2.7 Defective Materials & Work

Defective Materials & Work

Should defective materials and/or work be found at any time before final acceptance of the work, it shall be rejected. Rejected JSC Interior Panelling work shall be repaired and/or replaced to the satisfaction of the Contract Administrator, without delay and at no additional cost to the Principal.

SMARTSPEC