TABLE OF CONTENTS

Cladding & PreCladding 4
Stratco Profiled Metal Wall Cladding 4
Appendix 19
Stratco CGI Corrugated Building Product Information Sheet 19
Stratco 900 Building Product Information Sheet 19
Stratco Hiland Tray Building Product Information Sheet 19
Stratco S7 Building Product Information Sheet 19
Stratco Superdek Building Product Information Sheet 19
Stratco Trimline Building Product Information Sheet 19

SMARTSPEC

1 CLADDING & PRECLADDING

1.1 Preliminary

Refer to General Conditions of Contract and the Special Conditions in this Specification as appropriate. Read this section in conjunction with all other trade sections.

1.2 Compliance

Comply with the New Zealand Building Code 1992 including all revisions and amendments, Verification Methods where appropriate, and construction principles that are embodied in the Acceptable Solutions.

Comply with all relevant provisions and recommendations of:

1170.0:2002 SUPP1(AS/NZS)	Structural design actions - General principles - Commentary
1170.2:2011(AS/NZS)	Structural design actions - Wind actions
2728:2013(AS|NZS)	Prefinished/prepainted sheet metal products for interior/exterior building applications - Performance requirements
3604:2011(NZS)	Timber-framed buildings
NZBC F2	Hazardous Building Materials
NZMRM Code of Practice	NZ Metal Roof and Wall Cladding Code of Practice - Version 3.0

1.3 Stratco Profiled Metal Wall Cladding

1.3.1 Scope

Supply and install Stratco - Profiled Metal Wall Cladding, as specified herein, to the locations and details shown on the design drawings, complete with all necessary components and accessories required for proper installation and performance. All aspects of this work shall comply with the NZ Building Code, related Stratco - Profiled Metal Wall Cladding technical literature and publications (check http://www.stratco.co.nz or call (0800) 787 282 for the latest editions), and other relevant product manufacturers' recommendations.

No substitutions are permitted for Stratco - Profiled Metal Wall Cladding.

For the purpose of this specification, Stratco - Profiled Metal Wall Cladding is referred to as 'Profiled Metal Wall Cladding', and all 'Stratco' associated technical literature and publications, including the 'Stratco Product Technical Statement', installation instructions and drawings, are collectively referred to as the 'technical literature'.

Extent of work:

The following is a list and/or general description of the extent of the Stratco - Profiled Metal Wall Cladding works, which are more specifically defined in the contract documents, required for the completion of the contract works:

1.3.2 Requirements

1.3.2.1 Safety:

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

1.3.2.2 Warranty:

Warranty for Manufacturer or Supplier:

- 15 years minimum for coatings

Commence the warranty from the date of installation.

Warranty - Installer/ Applicator:

Warrant this work under normal environmental and use conditions against weatherproofing failure.

Workmanship – Refer to Supplier.

1.3.2.3 Substitutions:

The Stratco - Profiled Metal Wall Cladding shall be as specified herein and on the design drawings. The substitution of the Stratco - Profiled Metal Wall Cladding for an alternative brand is not permitted under any circumstances.

The substitution of the specified Stratco - Profiled Metal Wall Cladding or ancillary component for an alternative Stratco - Profiled Metal Wall system or ancillary component by the Contractor shall only be permitted with the Contract Administrator's written authorisation and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate an alternative Stratco - Profiled Metal Wall Cladding or ancillary component to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor.

1.3.2.4 Samples:

As required, provide samples of the specified Stratco - Profiled Metal Wall cladding for verification by the Contract Administrator.

1.3.2.5 Producer statement (PS3):

The Stratco - Profiled Metal Wall installer shall furnish a fully completed PS3 Producer Statement (Construction) at time of application for Code Compliance Certificate. The Producer Statement shall accurately reflect the scope of the installation of the Profiled Metal Wall Cladding in accordance with the consented drawings and specifications.

SMARTSPEC