IBS PRIMAflex™ Cavity System

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 3
- Components & Accessories 4
- Co-operation 6
- Workmanship 7
- Delivery & Handling 7
- Preparation 8
- Installation 9
- Fixing 12
- Completion 13

Compliances 13

SMARTSPEC

1 Specification Details

Trade Sections: Carpentry
Description:
Keywords: Carpentry, Independent Building Supplies, IBS, PRIMAflex™ Cavity System, fibre-cement cladding, fibre cement cladding, wall cladding, sheet cladding, fibre-cement sheet, fibre cement sheet, fibre-cement panel, fibre cement panel, panelling, sheeting, cavity cladding, cavity construction,

2 Clauses

2.1 Scope

Help Note:
This specification covers PRIMAflex™ fibre-cement sheet exterior panelling for exterior cladding applications only as defined by the PRIMAflex™ Cavity System BRANZ Appraisal.

If in doubt about any aspect of your specification please email info@ibs.co.nz, or call 0800 367 759.

For technical information on products to attach to this project, please visit productspec.co.nz/en/supplier/independent%20building%20supplies%20ltd.

2.1.1 Scope

Supply and install the PRIMAflex™ Cavity System, as specified herein, as fibre-cement sheet cladding to the locations identified on the drawings, complete with all system components and accessories required for proper installation and performance. All aspects of this work shall be in complete accordance with IBS PRIMAflex™ technical literature including the IBS PRIMAflex™ Design & Installation Guide (check www.ibs.co.nz, or email info@ibs.co.nz, or call 0800 500 338 for the latest editions), BRANZ Appraisal No.635, and other relevant product manufacturers' recommendations.

No substitutions are permitted for the PRIMAflex™ Cavity System.

For the purpose of this specification, all IBS PRIMAflex™ technical literature, including the PRIMAflex™ IBS Design & Installation Guide and the PRIMAflex™ Cavity System BRANZ Appraisal, is collectively referred to as the 'Technical Literature'.

The PRIMAflex™ Cavity System cladding is to be finished with a latex paint system; refer to separate specification section - Painting & Decorating.

2.1.2 Extent of Work

The following is a list and/or general description of the extent of the PRIMAflex™ Cavity System works, which are more specifically defined in the contract documents, required for the completion of the contract works:

SMARTSPEC

2.2 Requirements

Help Note:
Clause options listed below are optional - as applicable, select only those options according to project requirements.

If in doubt about any aspect of your specification please email info@ibs.co.nz, or call 0800 367 759.

2.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

2.2.2 Warranty

IBS PRIMAflex™ Product Warranty - according to warranty terms and conditions:
- 15 Years Warranty for PRIMAflex™fiber-cement panels supplied by IBS.
- Provide the warranty on the supplier's standard warranty form.
- Commence the warranty from the date of practical completion of the contract works.

2.2.3 Substitutions

The PRIMAflex™ Cavity System shall be as specified herein and on the design drawings. The substitution of the PRIMAflex™ fibre-cement materials for an alternative brand or material is not permitted under any circumstances.

The substitution of the PRIMAflex™ Cavity System materials specified for an alternative PRIMAflex™ Cavity System material by the Contractor shall only be permitted with the Contract Administrator's written authorisation and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate an alternative PRIMAflex™ Cavity System material to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor.

2.2.4 Inspections & Reporting

BCA inspections of the works shall take place at each of the stages scheduled in the Building Consent. Confirm a written programme to facilitate these inspections, including notification when each stage of the work is ready for inspection.

Carry out all necessary pre-installation and installation inspections for each area of the works.

Complete all necessary Pre-Installation Checklists, and all necessary Installation Checklists.

Complete all necessary Sign-Off Certificates before handing over completed work.

SMARTSPEC