Abodo Screening Timber

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 3
- Vulcan Screening 3
- Fixings 5
- Co-operation 6
- Workmanship 6
- Delivery & Handling 6
- Installation 7
- Completion 8

Compliances 8

SMARTSPEC

1 Specification Details

Trade Sections: Carpentry
Description:
Keywords: Carpentry, Abodo Wood, Abodo Screening Timber, timber, structural timber, structural timber framing, structurally graded framing timber, framing timber, framing, timber framing, kiln dried framing, kiln dried timber framing, kiln dried structural timber, kiln dried framing timber, stress graded timber, stress-graded timber, stress graded framing timber, stress-graded framing timber, Radiata, pine, Radiata timber, Radiata framing, Radiata framing timber, Radiata timber framing, structural Radiata, structural grade Radiata, machine stress graded timber, machine stress-graded timber, machine stress graded framing timber, machine stress-graded framing timber, treated timber, treated timber framing, treated framing timber, treated structural grade framing timber, Abodo Structural SG8, SG8 timber, SG8 framing, stress graded SG8, stress-graded SG8,
Boron treated framing timber, Boron treated timber framing, H1.2 treated framing timber, H1.2 treated timber framing, CCA treated framing timber, CCA treated timber framing, H3.2 treated framing timber, H3.2 treated timber framing, H4 treated timber framing, H5 treated timber framing, Vulcan Engineered, engineered timber, engineered framing, engineered timber posts, engineered timber beams,

2 Clauses

2.1 Scope

Help Note:
For technical enquiries contact Abodo Wood on 09 249 0100, or email info@abodo.co.nz.

For technical information on products to attach to this project, please visit productspec.co.nz/en/supplier/abodo%20wood.

2.1.1 Extent of Work

The following is a list and a general description of the extent of the Abodo Screening Timber works, which are more specifically defined in the contract documents, required for the completion of the contract works:

2.1.2 Scope

Supply and install Abodo Screening Timber, as specified herein, to the locations and screening timber elements identified on the drawings, complete with all accessories required for proper installation. All aspects of this work shall be in complete accordance with Abodo screening timber technical manuals and specifications (check abodo.co.nz, or email info@abodo.co.nz, or call 09 249 0100 for the latest editions), and other relevant product manufacturers' recommendations.

SMARTSPEC

No substitutions are permitted for Abodo Screening Timber.

2.2 Requirements

2.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

2.2.2 Substitutions

Abodo Screening Timber shall be as specified herein and as indicated on the approved drawings. The substitution of Abodo Wood branded products for alternative brands is not permitted under any circumstances.

The substitution of a specified Abodo Wood product for an alternative Abodo Wood branded product by the Contractor shall only be permitted with the Architect's/Designer's written authorisation, and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate alternative Abodo Wood branded products to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor.

2.2.3 Defective Materials & Work

Should defective materials and/or work be found at any time before the final acceptance of the work, it shall be rejected. Rejected Abodo Structural Timber materials and work shall be repaired and/or replaced to the satisfaction of the Architect/Designer, without delay and at no additional cost to the Principal.

Should a problem be encountered with any Abodo Wood product during use or delivery, immediately contact the Abodo Wood on 09 2490 100. Do not continue to use the product that is not performing to specification or expectation. Keep the product in question, and where possible, the document batch numbers and/or manufacturing details.

2.3 Vulcan Screening

Help Note:

For technical enquiries contact Abodo Wood on 09 249 0100, or email info@abodo.co.nz.

2.3.1 Vulcan Screening

Abodo Vulcan Screening. Engineered appearance-grade posts and beams manufactured from thermally modified Radiata pine (*Pinus radiata*), glue-laminated engineered with a vertical grain orientation. Suitable for above ground use in exterior and interior applications such as joinery, pergolas, screening, balustrades. Not suitable for heavy structural applications. Installed to the locations indicated on the approved drawings.

SMARTSPEC