StoStucco Plaster Cavity System

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 2
- StoStucco Render System 3
- Other Components & Accessories 4
- Co-operation 6
- Workmanship 6
- Delivery & Handling 7
- Preparation 7
- Installation 9
- Render System - Base Coat 11
- Render System - Mesh Coat 12
- Render System - Finishing Coat 13
- Protective Coating 15
- Completion 16

Compliances 17

SWARTSPEC

1 Specification Details

Trade Sections: Plasterwork
Description:
Keywords:

2 Clauses

2.1 Scope

2.1.1 Scope

Supply and install StoStucco Plaster Cavity System, as specified herein, to the locations identified on the design drawings, complete with all system components and accessories required for proper installation and performance. All aspects of this work shall be in complete accordance with Stoanz Ltd StoStucco Plaster Cavity System technical literature and drawings (check www.sto.co.nz, or email info@sto.co.nz, or call 04 801 4749 for the latest editions), BRANZ Appraisal No.605, and other relevant product manufacturers' recommendations.

No substitutions are permitted for StoStucco Plaster Cavity System.

For the purpose of this specification, all Stoanz Ltd StoStucco Plaster Cavity System technical literature and drawings and BRANZ Appraisal are collectively referred to as the 'Sto Technical Literature'.

2.1.2 Extent of Work

The following is a list and/or general description of the extent of the StoStucco Plaster Cavity System works, which are more specifically defined in the contract documents, required for the completion of the contract works:

2.2 Requirements

2.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

2.2.2 Sto Warranty

StoArmat Warranty with StoService Assurance - according to warranty terms and conditions:
- 20 Years' Warranty for StoStucco Plaster Cavity System incorporating StoArmat Classic mesh-reinforced render.
- Provide the warranty on the supplier's standard warranty form.
- Commence the warranty from the date of practical completion of the contract works.

SMARTSPEC

2.2.3 Substitutions

The StoStucco Plaster Cavity System shall be as specified herein and on the design drawings. The substitution of the StoStucco Plaster Cavity System for an alternative brand, system or cladding material is not permitted under any circumstances.

The substitution of a specified Sto branded product for an alternative Sto branded product by the Contractor shall only be permitted with the Contract Administrator's written authorisation and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate an alternative Sto branded product to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor.

2.2.4 Samples

Submit a clearly identified 300 x 300mm sample of the specified StoStucco render system, including finish coat texture and facade paint and colour, for assessment by the Contract Administrator - do not proceed until the samples have been approved.

2.2.5 Inspections & Reporting

BCA inspections of the works shall take place at each of the stages scheduled in the Building Consent. Confirm a written programme to facilitate these inspections, including notification when each stage of the work is ready for inspection.

Carry out all necessary pre-installation and installation inspections for each area and stage of the works.

Complete all necessary Pre-Installation Checklists, and all necessary Installation Checklists.

Complete all necessary Sign-Off Certificates before handing over completed work.

2.2.6 Quality Assurance

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of the works are carried out to the highest standard.

2.2.7 Defective Materials & Work

Should defective materials and/or work be found at any time before the final acceptance of the work, it shall be rejected. Rejected StoStucco Plaster Cavity System work shall be repaired and/or replaced to the satisfaction of the Contract Administrator, without delay and at no additional cost to the Principal.

2.3 StoStucco Render System

2.3.1 StoStucco Render System

StoStucco Render System. Refer to subsequent Render System clauses.

System Renders & Protective Coatings:
- Base Render: StoLevell Novo, or LevelLite Mineral Render

SMARTSPEC