GIB® Plasterboard Linings

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 2
- Performance 4
- GIB® Plasterboard Linings 5
- GIB-Cove® 9
- Components & Accessories 10
- Level of Finish 14
- Co-operation 15
- Workmanship 15
- Delivery & Handling 16
- Preparation 16
- Installation 18
- Completion 24

Compliances 25

SWARTSPEC

1 Specification Details

Trade Sections: Carpentry
Description:
Keywords: Carpentry, GIB, Winstone Wallboards, plasterboard, wall lining, ceiling lining, GIB® Standard Plasterboard,
GIB Wideline®, GIB Ultraline®, GIB Toughline®, GIB Braceline® & GIB Noiseline®, GIB Aqualine®, GIB Fyreline®, GIB Superline®, GIB X-Block®, GIB® Quietline®, GIB-Cove®,

2 Clauses

2.1 Scope

Help Note:
For further information and technical advice about GIB® Plasterboard Linings and GIB® Systems refer to the GIB® Site Guide or contact the GIB® Helpline on 0800 100 442.

For technical information on products to attach to this project, please visit productspec.co.nz/en/supplier/gib%c2%ae.

2.1.1 Scope

Supply and install GIB® Plasterboard Linings specified herein, as sheet lining materials to the walls, ceilings and other elements identified on the drawings, complete with all accessories required for proper installation, finishing and performance. All aspects of this work shall be in complete accordance with the current GIB® Site Guide and relevant GIB® Systems literature (check www.gib.co.nz, or call 0800 100 442 for the latest editions), and other relevant product manufacturers' recommendations.

No substitutions are permitted for GIB® Plasterboard Linings, GIB® Systems or GIB® System components and accessories.

This specification must be read in conjunction with relevant GIB® Systems specifications - GIB® EzyBrace® Systems, GIB® Fire Rated Systems, GIB® Noise Control Systems, GIB® Aqualine® Wet Area Systems, GIB® X-Block® Systems, GIB® Quietline®, GIB® Intertenancy Barrier System, and GIB® Rondo® Metal Batten Systems - and other specifications sections, as they are interrelated.

2.2 Requirements

Help Note:
For further information and technical advice about GIB® Plasterboard Linings and GIB® Systems refer to the GIB® Site Guide or contact the GIB® Helpline on 0800 100 442.

SMARTSPEC

2.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

2.2.2 Warranty

GIB® Product & System Warranty:

GIB Systems Durability.
The following systems have, unless stated otherwise in GIB® technical literature, a serviceability life in excess of that stated and satisfy the requirements of NZBC Clause B2 Durability:
15 Years:
- GIB Aqualine® Wet Area Systems.

50 Years:
- GIB® Fire Rated Systems
- GIB EzyBrace® Systems
- GIB X-Block® Systems
- GIB Noise Control® Systems.

Provide the GIB® Product & System Warranty on the manufacturer's standard warranty form. Commence the warranty from the date of practical completion of the contract works.

Include with the warranty: a copy of the completed GIB® Installation Sign-Off sheet, and the GIB® Plasterboard Lining Systems Care and Maintenance bulletin.

2.2.3 AWCI Membership

Installation of GIB® Plasterboard Linings and associated GIB® Systems shall be carried out by a registered member of the Association of Wall and Ceiling Industries of New Zealand Inc. (AWCI). If not already provided and if requested, submit evidence of AWCI membership and relevant experience.

2.2.4 Quality Assurance

Ensure that the installation and finishing of GIB® Plasterboard Linings and associated GIB® Systems comply in all respects with the approved design drawings and specifications, and Building Consent.

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of work are carried out to the highest standard.

2.2.5 Inspection & Acceptance of GIB® Plasterboard Linings

Carry out all necessary pre-installation, installation and finishing inspections of GIB® Plasterboard Linings for each area of work in accordance with the requirements of the GIB® Site Guide and associated industry Code of Practice (AWCI) recommendations.

SMARTSPEC