Plymasters Interior Lining System

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 2
- Performance 4
- Euro Birch Range 4
- Interior lining Range 6
- Classique Range 12
- Colour Oak Range: 16
- Furnier Range 20
- HPL Italia Range 25
- HPL Supalam Range 32
- Rustica Range 35
- Techno 38
- Marine Grade Plywood 40
- Ancillary Components & Accessories 43
- Surface Appearance 43
- Finish Coating 44
- Co-operation 44
- Workmanship 45
- Delivery & Handling 45
- Preparation 46
- Installation 47
- Fixing 47
- Completion 48

Compliances 49

SWAPETSPEC

1 Specification Details

Trade Sections: Concrete, Carpentry, Joinery
Description: Interior Lining system
Keywords: Plywood, Interior Linings, Prefinished Veneer Panels, Plymasters, Plywood, MDF, Laminate Panels, Marine Plywood, Timber Veneer Panels

2 Clauses

2.1 Scope

Help Note:
For technical enquiries contact Plymasters on 0800344112 or e-mail sales@plymasters.co.nz or head to the website www.plymaster.co.nz

For technical information on products to attach to this project, please visit https://productspec.co.nz/en/supplier/plymasters

2.1.1 Scope

The following is a list and/or general description of the extent of the Plymasters Interior Lining System works, which are more specifically defined in the contract documents, required for the completion of the contract works:

Supply and install Plymasters Interior Lining System, as specified herein, to the locations identified on the drawings, complete with all components and accessories required for proper installation and performance. All aspects of this work shall be in complete accordance with Plymasters 'technical literature' (check https://plymasters.co.nz/categories/products, or email sales@plymasters.co.nz, or call 0800 344 112 for the latest editions), other relevant product manufacturers' recommendations, and the New Zealand Building Code.

No substitutions are permitted for Plymasters Interior Lining System products.

This specification should be read in conjunction with other specification sections, in particular Painting & Decorating, as they are interrelated.

2.2 Requirements

2.2.1 Safety:

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

SMARTSPEC

2.2.2 Warranty – Product:

Plymasters Product Warranty - as applicable and according to warranty terms and conditions:

- Three year warranty for Plymasters Interior lining System materials.
- Provide the warranty on the Plymasters standard warranty form.
- Commence the warranty no later than three days after delivery.

2.2.3 Substitutions:

Plymasters Interior Lining System materials shall be as specified herein and as indicated on the design drawings. The substitution of the specified Plymasters Interior Lining System materials for an alternative brand or material is not permitted under any circumstances.

The substitution of a specified Plymasters plywood material for an alternative Plymasters plywood material by the Contractor shall only be permitted with the Contract Administrator's written authorisation, and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate an alternative Plymasters plywood material to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor

2.2.4 Samples:

Submit a clearly identified, 300 x 300mm sample of each Plymasters plywood material specified for assessment by the Contract Administrator - do not proceed until the samples have been approved.

2.2.5 Quality Assurance:

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of the works are carried out to the highest standard.

Ensure that the installation and finishing of Plymasters Interior Lining System comply in all respects with the approved design drawings and specifications, and Building Consent.

2.2.6 Inspections & Reporting:

BCA inspections of the works shall take place at each of the stages as scheduled in the Building Consent. Confirm a written programme to facilitate these inspections, including notification when each stage of the work is ready for inspection.

Carry out all necessary pre-installation and installation inspections for each area of the works.

Complete all necessary Pre-Installation Checklists, and all necessary Installation Checklists.

Complete all necessary Sign-Off Certificates before handing over completed work.

2.2.7 Defective Materials & Work:

Should defective materials and/or work be found at any time before the final acceptance of the work, it shall be rejected. Rejected Plymasters Interior Lining System work shall be repaired and/or replaced

SMARTSPEC