Megafloor™ Polished Concrete

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 2
- Samples 5
- Megafloor™ Exposure 5
- Megafloor™ Finish 6
- Components 10
- Co-operation 11
- Workmanship 11
- Delivery & Handling 11
- Preparation 12
- Installation 13
- Protection 24
- Completion 24

Compliances 25

SWARTSPEC

1 Specification Details

Trade Sections: Concrete, Specialist Services & Equipment
Description:
Keywords: Concrete, Polished Concrete Ltd, Megafloor Polished Concrete, concrete grinding, concrete polishing, concrete floors, concrete slabs, honed concrete, concrete honing, exposed aggregate concrete, textured concrete, brush hammered concrete, concrete surfaces, Megafloor High Street, Megafloor Urban, Megafloor Beach House, Megafloor Warehouse, Megafloor Al Fresco, Premium Finish, Classic Finish, Standard Finish, Ground Surface Finish, Brush Hammer Finish,

2 Clauses

2.1 Scope

Help Note:
For technical advice and specification guidance, email Megafloor at info@megafloor.co.nz or call 0800 476 5474.

For technical information on products to attach to this project, please visit productspec.co.nz/en/supplier/megafloor.

2.1.1 Scope

Supply and install Megafloor™ Polished Concrete from Polished Concrete Ltd, as specified herein, to the locations identified on the design drawings, complete with all system components and accessories required for proper installation and performance. All aspects of this work shall be in complete accordance with Polished Concrete Ltd requirements and technical literature (check www.megafloor.co.nz, email info@megafloor.co.nz, or call 0800 476 5474 for the latest editions), and other relevant product manufacturers' recommendations.

No substitutions are permitted for Megafloor™ Polished Concrete.

2.1.2 Extent of Work

The following is a list and general description of the extent of the Megafloor™ Polished Concrete works, which are more specifically defined in the contract documents, required for the completion of the contract works:

2.2 Requirements

Help Note:
Clause options listed below are optional - as applicable, select only those options according to project requirements.

SMARTSPEC

For technical advice and specification guidance, email Megafloor at info@megafloor.co.nz or call 0800 476 5474.

2.2.1 Safety

Comply with the Health and Safety at Work Act 2015 (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

2.2.2 Warranty

Polished Concrete Ltd Warranty - according to the warranty conditions.
- Megafloor™ Premium Finish: 5 Years' Warranty for Materials and Workmanship - for all Megafloor™ Premium Finish surfaces.
- Megafloor™ Classic Finish: 3 Years' Warranty for Materials and Workmanship - for all Megafloor™ Classic Finish surfaces.
- Megafloor™ Standard Finish: 2 Years' Warranty for Materials and Workmanship - for all Megafloor™ Standard Finish surfaces.
- Provide the warranty on the Megafloor™ standard warranty form.
- Commence the warranty from the date of practical completion of the contract works.

2.2.3 Substitutions

Megafloor™ Polished Concrete floor finishes shall be as specified herein and on the design drawings. The substitution of Megafloor™ Polished Concrete floor finishes for alternative brands, systems or finishes is not permitted under any circumstances.

The substitution of a specified Megafloor™ Polished Concrete floor finish for an alternative Megafloor™ finish shall only be permitted with the Contract Administrator's authorisation, and shall be at no additional cost to the Principal. Should any resultant extra work and/or redesign work be required to accommodate alternative Megafloor™ Polished Concrete floor finishes to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor.

2.2.4 Quality Assurance

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of Megafloor™ Polished Concrete work are carried out to the highest standard.

2.2.5 Pre-Start Meeting - New Concrete Slabs

Megafloor™ Polished Concrete Pre-Start Meeting - for New Concrete Slabs. Before the commencement of concreting and the Megafloor™ Polished Concrete works, convene an on-site pre-start meeting with the necessary parties, including the concrete placer and the appointed Polished Concrete Ltd technical representative, to review and confirm:
- the concrete specification; and
- concrete placement procedures and requirements; and
- the Megafloor™ Polished Concrete floor specification, procedures and methodology; and
- Megafloor™ Polished Concrete samples; and
- requirements for cordoning off and protecting all stages of Megafloor™ Polished Concrete works;