Forté Interior Paneling

TABLE OF CONTENTS

Specification Details 2
Clauses 2
- Scope 2
- Requirements 2
- Tactile T&G Panelling 4
- Muuro 5
- Salvare Spruce Panelling 6
- Imondi Oak Panelling 10
- Accessories 11
- Co-operation 12
- Workmanship 12
- Delivery, Handling & Preparation 13
- Installation 13
- Completion 13

Compliances 13

SMARTSPEC

1 Specification Details

Trade Sections: Carpentry
Description: Forté Interior Paneling- Forté design and source an exceptional range of specialist timber products for flooring, walls, ceilings, and decking, all suited to New Zealand's diverse climates and lifestyles
Keywords: Carpentry, Forté Interior Panelling, Forte Flooring, Wall & Ceiling Coverings, engineered wood, wood planks, wooden planks, timber planks, wooden boards, wood boards, timber boards, paneling, timber panels, wood panels, wooden panels, wall panels, ceiling panels, wall plank, ceiling plank, wall linings, ceiling linings, wall finishes, ceiling finishes, decorative finishes, interior finishes, interior linings, interior walls, interior ceilings, wood finish, timber finish.

2 Clauses

2.1 Scope

Help Note:
For technical information on products to attach to this project, please visit Forté.co.nz

Additonal information can be found at Forte Refined Timber, Professional Resources.

2.1.1 Scope

Supply and install Forté Interior Panelling, as specified herein, to the locations, layout and details shown on the drawings, complete with all accessories required for proper installation. All aspects of this work shall be in complete accordance with the manufacturer's technical literature and Forté requirements (check www.forte.co.nz, or email info@forte.co.nz, or call 0508 35 66 77 for the latest editions), and other relevant product manufacturers' recommendations.

No substitutions are permitted for Forté Interior Panelling.

2.1.2 Extent of Work

The following is a list and general description of the extent of the Forté Interior Panelling works, which are more specifically defined in the contract documents, required for the completion of the contract works:

2.2 Requirements

Help Note:
Clause options listed below are optional - as applicable, select only those options according to project requirements.

For technical advice and specification guidance, contact Forté on 0800 445 494.

SMARTSPEC

2.2.1 Safety

Comply with the Health and Safety at Work (HSWA), and with all relevant Health and Safety at Work Regulations 2016, and with all relevant WorkSafe New Zealand (WorkSafe) Approved Codes of Practice and WorkSafe Information and Guidance, particularly those for construction and building maintenance.

2.2.2 Warranty, Product

Forté Flooring Ltd Product Warranty - according to the warranty conditions.
- For all Wall and Ceiling Coverings supplied by Forté Flooring Ltd.
- Provide the Product Warranty on the Forté Flooring Ltd standard warranty form.
- Commence the warranty from the date of practical completion of the contract works.

2.2.3 Substitutions

Forté Interior Paneling shall be as specified herein and as indicated on the design drawings. The substitution of Forté Flooring Ltd supplied Forté Interior Paneling for an alternative or material is not permitted under any circumstances.

The substitution of a specified Forté Interior Paneling product for an alternative Forté Flooring product by the Contractor shall only be permitted with the Contract Administrator's written authorisation, and shall be at no additional cost to the principal. Should any resultant extra work and/or redesign work be required to accommodate alternative Forté Interior Paneling products to satisfy design, performance and compliance requirements, then the cost of these shall be borne by the Contractor.

2.2.4 Samples

Submit a clearly identified full-size sample of each wall and/or ceiling covering range and colour specified, for signed approval by the Contract Administrator - do not proceed until the samples have been approved.
Where a colour has not been specified, submit a clearly identified sample of each colour for the range specified, for colour selection and signed approval by the Contract Administrator.

2.2.5 Quality Assurance

Maintain and comply with industry-recognised quality control and assurance procedures to ensure that all stages of the works are carried out to the highest standard.

2.2.6 Inspection & Reporting

Carry out all necessary pre-installation, installation and sign-off inspections of the works for each area of work in accordance with Forté Flooring Ltd requirements and industry best-practice recommendations.
Complete all necessary Pre-Installation and Installation Checklists.
Complete all necessary Sign-Off Certificates before handing over completed work.